A REPORT ON AIR QUALITY MONITORING RESULTS IN NEW BRUNSWICK

FOR THE YEAR 1998

New Nouveau Brunswick

Department of the Environment

New Nouveau Brunswick

New Brunswick Department of the Environment

NEW BRUNSWICK

AIR QUALITY MONITORING RESULTS

FOR THE YEAR

1998

Technical Report T-9904

Environmental Evaluation Section
New Brunswick Department of the
Environment
P.O. Box 6000
Fredericton
New Brunswick
E3B 5H1

December 1999

EXECUTIVE SUMMARY

This report summarises air quality monitoring data in New Brunswick for 1998. The report is intended to provide a convenient summary of air quality results for general public information, with emphasis on air quality assessment in relation to existing air quality standards and objectives. Long term trend data are also presented for representative sites. In New Brunswick, air quality standards for carbon monoxide, sulphur dioxide, hydrogen sulphide, nitrogen dioxide and total suspended particulate are specified in the *Air Quality Regulation of the Clean Air Act*.

Air quality has been monitored in New Brunswick since the 1960's, when several short-term studies were carried out in Saint John. The emphasis on air monitoring has steadily increased over the years. Air contaminants presently covered by provincial standards were measured at 48 sites in 7 regional monitoring networks across the province during 1998. Acid rain was measured at 13 additional sites in 1998. Inhalable particulate matter (PM_{10}) and ground-level ozone were also monitored at a number of locations, although no standards are yet in effect in New Brunswick for these substances. All monitored data were acquired and reviewed by NBDOE, either continuously, or in the form of monthly reports, during the year.

Compliance with standards was reviewed in conjunction with specific industry episode control plans, which are required under the *Air Quality Regulation* in certain areas. This report presents summary statistics from all monitoring sites in the province, as well as additional statistical data (in chart form) in an Appendix.

Compliance with legislated air quality standards was generally good to excellent during 1998, although variations were noted for some pollutants, as detailed below.

There was 100% compliance with standards in effect for carbon monoxide and nitrogen dioxide at all monitoring sites. For sulphur dioxide, hydrogen sulphide and total suspended particulate, some exceedances of the applicable standards or objectives were registered at specific locations, while other locations were in full compliance. Concentrations of ozone and PM_{10} particulate matter also exceeded recommended guidelines in effect for these substances nationally, or in other jurisdictions, on a limited number of occasions.

Episode control programs, which are in effect for some major emission sources across New Brunswick, were seen to be effective in reducing the number of occasions on which elevated levels of air pollutants occur. Notable in this regard is the program in place in Saint John, which has enabled almost 100% compliance with a very strict ambient standard for sulphur dioxide. The Department of the Environment continually works with industries to implement the necessary control technologies to ensure compliance with air quality standards.

An examination of air quality trends at sites with long records indicates that, since the late 1970s' and 1980's, air quality has improved for all pollutants currently being measured, with the possible exception of ground level ozone. Levels of sulphur dioxide, total suspended particulate, and PM_{10} have fallen significantly over the past 15-20 years. Levels of carbon monoxide and nitrogen dioxide have also generally fallen.

The management of air quality in New Brunswick is based upon the principles set out in the *Clean Air Act*. The Department's goal is full compliance with regulatory standards, and the prevention of degradation of air quality in the province.

Feedback

We are interested in your opinions and feedback on this report. All suggestions will be considered, and if possible, incorporated in future reports. You may contact the Environmental Evaluation Section at (506) 457-4844, by fax at (506) 453-2265 or e-mail Robert Hughes at robert.hughes@gov.nb.ca with any comments.

Technical terms

Efforts have been made to keep the number of technical terms used in this report to a minimum. Technical terms which are used are shown for the first time in **bold type**. All these terms are defined or explained in a Glossary of Terms, which begins on page 50.

Report Authorship

Robert Hughes, Environmental Evaluation Section: Text, data summaries and research.

Acknowledgements

For assistance with data processing and chart preparation: Paul Seguin. Numerous other staff within NBDOE and from the industries operating monitoring networks provided valuable help with data provision. Special thanks to Stan Howe and Eric Blanchard of NBDOE for operation of the provincial monitoring sites, and the staff of the Saint John regional office of NBDOE for assistance with site operation in the Saint John area. Thanks to Sean Fortune for operation of the acid rain network and assistance with data and other queries.

Editorial comments were provided by Darryl Pupek, Elizabeth Hayward, Randy Piercey, Sean Fortune, Wilfred Pilgrim, Denis Marquis, Nabil Elhadi, Cheryl Heathwood and David Besner, which resulted in significant improvements to the report.

Thanks are also extended to site operators in the provincial acid rain monitoring network, including Alphonse Boissoneault (St. Maure), Marielle Morisette (Canterbury), Marie-Jeanne Cormier (Paquetville), Daniel Boudreau (Robertville), Rufus Goss (Pennfield), Leroy and Eleanor Johnson (Nictau), Murray MacFarlane (Holtville), Wanda and Bart Petley (Harcourt), Lori Lawlor (Lakewood Heights), Mae Stewart (Trout Brook), Gary and Nancy Kierstead (Coles Island), Luanne Brawn, Markle Brawn, Glen Eastwood, Robin Mazerolle, Basil Thompson (South Oromocto Lake) and Thane Watts (Fundy Park).

TABLE OF CONTENTS

EXECUTIVE SUMMARY

1. INTRODUCTION 1

2. AIR QUALITY LEGISLATION IN NEW BRUNSWICK 2

3. NATIONAL AIR QUALITY STANDARDS AND OBJECTIVES 3

4. NEW BRUNSWICK AIR QUALITY STANDARDS 4

5. OTHER AMBIENT AIR QUALITY CRITERIA
   A. Inhalable Particulate (PM_{10}) 5
   B. Ground Level Ozone 5

6. AIR POLLUTANTS - THEIR SOURCES AND EFFECTS 6
   A. Carbon Monoxide 6
   B. Nitrogen Dioxide 6
   C. Sulphur Dioxide 6
   D. Hydrogen Sulphide 6
   E. Ground-Level Ozone 7
   F. Total Suspended Particulate (TSP) 8
   G. Inhalable Particulate (PM_{10}) 8

7. MONITORING NETWORKS 9

8. AIR QUALITY MONITORING RESULTS FOR 1998 11
   A. SAINT JOHN 11
      A.1 Carbon Monoxide 12
      A.2 Nitrogen Dioxide 12
      A.3 Sulphur Dioxide 12
         A.3.1 Sulphur Dioxide episode control 14
      A.4 Ground Level Ozone 15
      A.5 Total Suspended Particulate 15
      A.6 Inhalable Particulate (PM_{10}) 15
      A.7 Hydrogen Sulphide 15
      A.8 Index of the Quality of the Air (IQUA) 16
   B. MIRAMICHI 19
      B.1 REPAP NETWORK 20
         B.1.1 Hydrogen Sulphide 20
         B.1.2 Total Suspended Particulate 20
      B.2 MILLBANK NETWORK 21
         B.2.1 Nitrogen Dioxide 21
         B.2.2 Sulphur Dioxide 21
         B.2.3 Total Suspended Particulate 21

   C. GRAND LAKE NB POWER 21
      C.1 Sulphur Dioxide 22
      C.2 Total Suspended Particulate 22

D. EDMUNDSTON FRASER INC. 23
D.1 Sulphur dioxide 23
D.2 Total Suspended Particulate 23

E. BELLEDUNE 24

E.1 BRUNSWICK MINING AND SMELTING 25
E.1.1 Sulphur dioxide 25
E.1.2 Total Suspended Particulate 25

E.2 NB POWER 26
E.2.1 Sulphur dioxide 26
E.2.2 Nitrogen dioxide 26

F. DALHOUSIE - NB POWER 27
F.1 Sulphur dioxide 27
F.2 Total Suspended Particulate 27

G. FREDERICTON
G.1 Total Suspended Particulate 28

H. MONCTON 28
H.1 Carbon Monoxide 28
H.2 Nitrogen Dioxide 28
H.3 Ozone 28
H.4 Index of the Quality of the Air 28

9. RURAL OZONE NETWORK - SOUTHERN NEW BRUNSWICK 29

10. ACID PRECIPITATION NETWORK 31
A. New England Governors/Eastern Canadian Premiers Acid Rain Action Plan 34
B. Canada-Wide Acid Rain Strategy for Post-2000 34

11. LONG TERM AIR POLLUTION TRENDS 35
A. Carbon Monoxide 35
B. Nitrogen Dioxide 36
C. Sulphur Dioxide 38
D. Ground Level Ozone 40
E. Total Suspended Particulate 43
F. Inhalable Particulate (PM_{10}) 46
G. Acid Rain 48

12. SUMMARY 49

APPENDIX I GLOSSARY OF TERMS AND ABBREVIATIONS 50

APPENDIX II CANADIAN NATIONAL AIR QUALITY OBJECTIVES 54

APPENDIX III DETAILED MONTHLY MONITORING RESULTS FOR 1998 55

REFERENCES 77

LIST OF FIGURES

Figure 1.	Locations of air quality monitoring sites in New Brunswick.	10
Figure 2.	Air quality monitoring sites in Saint John, New Brunswick.	11
Figure 3.	Air Quality Index Summary for 1998: Customs Building, Saint John.	17
Figure 4.	Air Quality Index Summary for 1998: Forest Hills, Saint John.	18
Figure 5.	Air Quality Index Summary for 1998: Hillcrest, Saint John.	18
Figure 6.	Air quality monitoring sites in the Miramichi Region.	19
Figure 7.	Air quality monitoring sites in the Grand Lake Network.	21
Figure 8.	Air quality monitoring sites in the Edmundston Network.	23
Figure 9.	Air quality monitoring sites in the Belledune Network.	24
Figure 10	Air quality monitoring sites in the Dalhousie Network.	27
Figure 11.	Air Quality Index summary for 1998: Moncton.	28
Figure 12.	Locations of ozone monitoring sites in New Brunswick (1996-97).	29
Figure 13.	Locations of acid rain monitoring sites in New Brunswick (1996-97).	32
Figure 14.	Acid Deposition for 1998 (kilograms per hectare per year of sulphate)	33
Figure 15.	Annual mean values of carbon monoxide at Post Office/Customs Building, Saint John, 1980-1998.	35
Figure 16.	Annual mean values of nitrogen dioxide at Forest Hills, Saint John, 1981-1998	36
Figure 17.	Annual mean values of nitrogen dioxide at Customs Building, Saint John, 1980-1998	37
Figure 18.	Annual mean values of sulphur dioxide dioxide at Forest Hills, Saint John, 1976-1998	38
Figure 19.	Annual mean values of sulphur dioxide at Post Office/Customs Building, Saint John, 1974-1998	39
Figure 20.	Annual mean values of ozone at Forest Hills, Saint John, 1980-1998	40
Figure 21.	Annual mean values of ozone at Post Office/Customs Building, Saint John, 1980-1998	41

Figure 22. Annual mean values of ozone at Point Lepreau, 1986-1998 ... 42

Figure 23. Annual mean total suspended particulate at Forest Hills, Saint John, 1978-1998. ... 43

Figure 24. Annual mean total suspended particulate at Provincial Building, Saint John, 1974-1998. ... 44

Figure 25. Annual mean total suspended particulate at Fredericton, 1975-1998 ... 45

Figure 26. Annual mean PM_{10} at Provincial Building, Saint John,1984-1998 ... 46

Figure 27. Annual mean PM_{10} at Forest Hills, Saint John,1989-1998. ... 47

Figure 28. Network-wide mean annual sulphate concentration in precipitation in New Brunswick, 1986-1998. ... 48

1. INTRODUCTION

This report summarises air quality information gathered during 1998 at monitoring locations across New Brunswick. A summary of data from the provincial **acid rain**[1] network is also included. This is a report on **ambient** (i.e. outdoor) air, which provides an indication of environmental quality in terms of air pollution. The report does not present or discuss quantities or trends in the emission of air contaminants. Information on air pollutant emissions in New Brunswick may be found in other reports (e.g. Delauriers, 1995; Environment Canada, 1998; Jaques, 1997) as well as on the internet at: http://www.ec.gc.ca/pdb/pdb_e.html.

Air quality has been monitored in New Brunswick since the 1960's, when several short-term studies were carried out. A number of federal and provincial agencies were involved in these co-operative projects, including the N.B. Department of Health. The New Brunswick Department of the Environment was established in 1971. Following this, more routine air quality monitoring began in areas known to be affected by industrial emissions. The accompanying box details a number of significant events in the history of air quality assessment in the Province.

In 1973 the permitting provisions of the first *Air Quality* ***Regulation*** took effect, whereby facilities releasing contaminants to the environment may do so only in accordance with terms set out in an Approval to Operate.

By the late 1970's, emphasis was also being placed on providing air quality monitoring information to the public. In 1979, an **air quality index** for public information was introduced in Saint John. The "**IQUA**" program - (Index of the Quality of the Air) was the first program of its kind to be operated in any Canadian municipality.

AIR QUALITY MILESTONES IN NEW BRUNSWICK

1961-1979

YEAR	EVENT
1961	Smoke and hydrogen sulphide monitoring carried out in Saint John by Transport Canada.
1964	Particulate pollution in Saint John studied by the Department of National Health and Welfare.
1970	Saint John District Medical Health Officer (DMHO) requested a federal study on air quality in the city.
1970	Dustfall and sulphur dioxide assessment began around the Belledune lead-zinc smelter.
1971	A five-week study of hydrogen sulphide, particulates and sulphur dioxide carried out in Saint John in response to the request of the DMHO.
1971	New Brunswick Department of Fisheries and Environment formed.
1971	Environment Canada, the federal environmental protection agency, established. The national Air Pollution Surveillance Network begins operation.
1971	New Brunswick *Clean Environment Act* entered force. National Air Quality Objectives Proposed.
1973	The first provincial Air Quality Regulations enacted, including smoke density standards, a permit process for operations emitting air pollution, and limits on the sulphur content of fuel oils.
1974	Two-way catalytic converters required for new motor vehicles, to control carbon monoxide and hydrocarbon emissions.
1975	Extensive vegetation injury from air pollution seen in Saint John in July. Monitoring networks reviewed and improved.
1976	A computerized data collection system set up to gather data from air pollution monitors in Saint John.
1978	Air quality monitoring initiated around the Dalhousie thermal generating station.
1979	The issuing of a twice daily air quality index system (Index of the Quality of the Air, or IQUA) began in Saint John.
1979	The *Air Quality Regulation* revised, with the inclusion of ambient air quality standards for the first time.

[1]See Appendix 1, Glossary of Terms and Abbreviations, for explanation of bold text.

2. AIR QUALITY LEGISLATION IN NEW BRUNSWICK

The basic framework for air quality management in New Brunswick is provided by the 1997 *Clean Air Act*. This Act broadly specifies the areas and activities in which the Minister of the Environment has authority to make regulations.

In comparison to the *Clean Environment Act*, the *Clean Air Act* is more comprehensive and detailed legislation. It also places major emphasis on providing information to the public and encouraging opportunities for public involvement in decision-making.

Regulations are created under such Acts in accordance with the authority they provide, and set out the detailed requirements which must be followed by individuals or organisations who are subject to the legislation.

Since 1973, the *Air Quality Regulation* has been the Province's principal regulatory tool in this field and, with some recent revisions, it continues to apply under the *Clean Air Act*. It sets out detailed requirements and provisions for a wide range of air quality management issues. Provincial air quality **standards** have also been contained in this regulation since 1979.

Other regulations which are used to manage air quality cover issues such as **Ozone** Depleting Substances. As part of the more comprehensive *Clean Air Act*, additional regulations have been prepared, including the Administrative Penalties Regulation (which came into force in July 1998) and the *Public Participation Regulation* (under continuing development).

These new regulations are aimed at providing the Province with additional options to promote compliance, and formalising procedures for public review of **Certificates of Approval** for major emission sources, as well as the process of setting or revising air quality **objectives** for the Province.

AIR QUALITY MILESTONES IN NEW BRUNSWICK
1980-1998

YEAR	EVENT
1980	The IQUA index reached the very poor range during a serious episode in Saint John in late July and early August, featuring high levels of sulphur dioxide and ozone.
1980	Air quality monitoring started in Edmundston to assess the impact of the Fraser pulp mill.
1987	Three-way catalytic converters required on new motor vehicles, which reduce emissions of nitrogen oxides, as well as carbon monoxide and hydrocarbons.
1987	New Brunswick signs acid rain reduction agreement with Federal Government.
1988	Air quality monitoring established around the Grand Lake thermal generating station.
1989	Monitoring begun in Miramichi around the REPAP paper mill (then the MPPC mill)
1990	Leaded gasoline banned.
1991	Air quality monitoring started around the thermal generating station at Millbank and future site at Belledune.
1993	The provincial *Clean Air Strategy* released, outlining long term plans for air quality protection, enhancement and management.
1993	The smog advisory program (joint program with Environment Canada) began in southern counties of NB, providing public forecasts of high ozone levels.
1995	Air Resource Management Area (ARMA) Committee established in Saint John. The sulphur dioxide standard in Saint John, Kings and Charlotte counties reduced by 50%.
1996	ARMA committees established in Edmundston and Bathurst.
1997	ARMA committees set up in Dalhousie/Campbellton and Miramichi. *Clean Air Act* received government assent.
1997	IQUA issued in Saint John three times daily and available on the Internet. Daily forecasts of ground-level ozone released to the media for Fundy counties of southern New Brunswick (joint program with Environment Canada).
1997	*Clean Air Act* came into force on December 15.

The *Clean Air Act* and its associated regulations are intended for the management of outdoor air quality. Air quality in buildings is regulated by health legislation, including the Health Act and the *Occupational Health and Safety Act*.

3. NATIONAL AIR QUALITY STANDARDS AND OBJECTIVES

Air quality management in Canada is primarily a provincial responsibility, although the Federal Government has a key mandate to carry out monitoring and research, as well as manage air issues which have a trans-boundary or international component. An example is the long range movement of air pollutants across provincial or international boundaries, such as those which cause acidic precipitation and **ground level ozone**.

Canadian air quality objectives are developed by a national committee (the Working Group on Air Quality Objectives and **Guidelines**) which includes representation from federal and provincial health and environment officials. When finalised through the Working Group process, the resulting 'National Ambient Air Quality Objectives' are incorporated in federal legislation under the *Canadian Environmental Protection Act*.

The goal of this process is to ensure some degree of uniformity across the country. Provinces then have the opportunity to incorporate these national objectives in their own environmental legislation. A complete listing of Canada's existing National Air Quality Objectives is contained in Appendix II.

National Objectives cover the major air pollutants of concern. Individual provinces, however, are able to develop additional air quality objectives or guidelines, if deemed necessary for environmental management in their particular jurisdiction. An example of this would be New Brunswick's decision in 1995 to adopt ambient air quality standards for **sulphur dioxide (SO_2)** in the southern part of the Province (such as the one-hour level of 17 parts per hundred million), which are twice as stringent as the existing National Objectives for this substance.

Recently, a new system for environmental standard-setting has begun, under the guidance of the Canadian Council of Ministers of the Environment, a national body made up of environment Ministers from the federal, provincial, and territorial governments. This process aims to set "Canada Wide Standards" (CWS) for air, water, and possibly soils and sediments. The focus will be on setting environmental quality standards which are based on sound science, with the aid of stakeholder public input. Other aspects of the CWS process include a consideration of socio-economic and technical issues as the standards are determined, the incorporation of an implementation plan for each standard, and a commitment for public reporting on the achievement of the standards.

The National Working Group on Air Quality Objectives and Guidelines periodically reviews the latest scientific work dealing with the effects of pollutants on human health, and the environment in general. Based on these reviews, the existing National Air Quality Objectives are revised as required. New objectives may also be proposed. For example, a new objective for Fine **Particulate** Matter is now under development, and the objective for ground-level ozone is currently being revised.

With the exception of the objective for ground level ozone, New Brunswick has included all National Air Quality Objectives in its *Air Quality Regulation* since 1979. This action has the effect of giving such objectives legal status through the *Air Quality Regulation's* approval process.

In the case of pollutants such as ground level ozone, the management approach in New Brunswick involves reducing the precursor emissions wherever possible, together with concerted regional control efforts, since the majority of ground level ozone measured in New Brunswick originates in the north-eastern United States and, to a lesser extent, southern Ontario and Quebec. This involves federally-led negotiations with States and Provinces which lie upwind from our western border. Precursor emissions are the substances which eventually lead to the formation of the pollutants themselves. For example, ground level ozone results from photo-chemical reactions in the air involving **NOx (nitrogen oxides)** and **VOCs**. In this case, NO_X and VOCs are precursors.

On a continental basis, New Brunswick's geographical position is downwind from some of the most heavily populated and industrialised regions of North America. This is why the Province's 1993 Clean Air Strategy has emphasised the need for a special focus on regional air quality management.

4. NEW BRUNSWICK AIR QUALITY STANDARDS

The New Brunswick *Air Quality Regulation* presently defines standards for five pollutants - carbon monoxide, nitrogen dioxide, sulphur dioxide, **total suspended particulates** and **hydrogen sulphide**. These numeric standards are indicated in the following table.

NEW BRUNSWICK AIR QUALITY STANDARDS				
Pollutant	**Averaging period**			
	1 hour	**8 hour**	**24 hour**	**1 year**
Carbon monoxide	30 **ppm**	13 ppm		
Hydrogen Sulphide	11 **ppb**		3 ppb	
Nitrogen dioxide	210 ppb		105 ppb	52 ppb
Sulphur dioxide*	339 ppb (34 **pphm**)		113 ppb (11 pphm)	23 ppb (2.3 pphm)
Total suspended particulate			120 **micrograms/m³**	70 micrograms/m³

* These standards for sulphur dioxide are 50% lower in Saint John, Charlotte and Kings counties.

These figures are identical to Canada's National Air Quality Objectives, with the exception of the more stringent standards for sulphur dioxide in three southern N.B. counties, noted in the table above.

5. OTHER AMBIENT AIR QUALITY CRITERIA

A. Inhalable Particulate (PM_{10})

There are presently no National Objectives for PM_{10} in Canada. Some existing standards in other areas are shown in the following table. These standards (primarily those from the Greater Vancouver Regional District and the U.S.A.) are currently used as reference points for evaluation of any PM_{10} data gathered in NB.

PM_{10} Standards in Various Jurisdictions (micrograms per cubic metre)		
Jurisdiction (date)	**Averaging period**	
	24 hour	**1 year**
GVRD (Vancouver) (1994)	50	30
Newfoundland (1997)	50	-
United States (1987; revised 1997)	150	50
California (1982)	50	30
Australia (1998)	50	-

Note: Newfoundland also adopted a 24-hour objective of 25 micrograms per cubic metre for **$PM_{2.5}$** in 1997..

B. Ground Level Ozone

As with PM_{10}, there is no New Brunswick standard in effect for ground level ozone. For evaluation purposes, the existing National Objectives for ozone are used as a reference and are shown in the following table. Additional information on the National Air Quality Objectives is contained in Appendix II. Note that New Brunswick is participating in the development of Canada-wide standards for both PM_{10}, $PM_{2.5}$, and ozone. In addition, New Brunswick is providing input for the development of an Ozone Annex to the Canada-US Air Quality Agreement. Work on the Annex began during 1999. The Annex is expected to formally recognise the geographic regions in Canada and the US where specific control measures must be applied to reduce ozone formation. It will also deal with emission caps or ceilings; technical limits on certain industrial processes; scientific work such as data sharing, mapping and interpretation, and data reporting. The development of this international policy document is seen as potentially useful in the continuing effort to obtain the required emission controls in regions upwind of New Brunswick.

National Ambient Air Quality Objectives for Ozone (ppb)			
Average period	Desirable Level	Acceptable Level	Tolerable Level
1 Hour	51	82	153
24 Hours	15	25	-
1 Year	-	15	-

Note: for an explanation of the different levels, see Appendix II.

6. AIR POLLUTANTS - THEIR SOURCES AND EFFECTS

Basic information is presented in the following sections about the pollutants covered by regulatory ambient standards in New Brunswick. The sources of such pollutants are also discussed, as well as their effects on human health and the environment.

A. Carbon Monoxide

Carbon monoxide (**CO**) is a colourless, odourless and tasteless gas. Major sources include motor vehicles, home heating systems, and refuse burning. Outdoors, CO is generally a problem pollutant only in congested urban centres with high traffic density, especially in winter, as vehicle engines produce more pollution in cold weather. In some traffic conditions, drivers and passengers in vehicles may be exposed to higher levels of CO than pedestrians in city streets. Malfunctioning or badly-vented heating furnaces or stoves may also produce dangerous levels of CO in buildings.

If inhaled, CO quickly enters the blood stream, where it reduces the ability of the blood to deliver oxygen to the organs and tissues of the body. The health impact of CO is most serious for those who suffer from **cardiovascular** disease, although healthy individuals are also affected at higher concentrations. Exposure to elevated levels is associated with numerous symptoms, including headache, fatigue, nausea, and impairment of vision. Work capacity, learning ability and the ability to perform complex tasks are reduced (Stewart, 1975; USEPA, 1980; Ritchie, 1991; CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1994; 1998).

B. Nitrogen Dioxide

Nitrogen dioxide (**NO_2**) in high concentrations is a reddish gas with a sharp, pungent smell. It is corrosive and can assist the start and spread of fire. Most NO2 found in the outdoor environment is not the result of direct emissions. Instead, it forms from nitric oxide (NO), which is emitted by many combustion sources, especially those which operate at high temperatures and pressures.

Motor vehicle engines meet both these characteristics, and are a major source of NO, which reacts quite rapidly with ozone in the air to form NO_2. Collectively, NO and NO_2 are often referred to as nitrogen oxides or NO_x. Thermal electricity generating stations and large heating boilers are other major sources of NO_x.

Nitrogen dioxide can irritate the lungs and lower resistance to respiratory infection. It also has an adverse effect on materials (i.e., corrosion of metals, fading of fabric dyes, degradation of rubber, etc.) and can damage vegetation (CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1987a).

As noted earlier, NO_2 also plays an important role in the formation of ground-level ozone, by reacting with **hydrocarbons** in the presence of sunlight, and contributes to the formation of acid rain and visibility-reducing haze, or **smog**.

C. Sulphur Dioxide

Sulphur dioxide (SO_2) is a colourless gas with a characteristic smell, like that of a struck match. When levels reach between 0.3 to 1.0 parts per million (ppm), it is generally detectable as an acidic taste in the air. SO_2 dissolves very readily in water, eventually forming sulphuric acid. SO_2 is one of the most significant pollutants in many industrialised nations: it is often emitted as a result of burning sulphur-containing fuels, and by metal smelters and oil refineries. Emissions of SO_2 from motor vehicles are relatively minor.

Health effects associated with exposure to high concentrations of sulphur dioxide include breathing discomfort, respiratory illness, alterations in the lung's normal defences, and aggravation of existing respiratory and cardiovascular disease. People with **asthma**, chronic lung or heart disease are the most sensitive to SO_2. Apart from effects on human health, SO_2 can also directly damage the leaves of trees, and agricultural crops. (Environment Canada, 1985; CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1987b). SO_2 also has important indirect impacts by contributing to acid rain, which acidifies lakes and rivers, speeds up the corrosion of masonry and metal objects, and removes essential elements from the soil. Sulphur dioxide also contributes to the formation of **acid aerosols** (fine acidic particles), which may have detrimental health effects. These small particles cause a visual haze, which affects the enjoyment of scenic vistas and has an effect on the earth's **radiation balance**.

D. Hydrogen Sulphide

Hydrogen sulphide (**H_2S**) is a colourless gas with a characteristic smell of rotten eggs. H_2S is flammable and can form an explosive mixture with air or oxygen. Common sources of H_2S include pulp and paper mills, oil refineries, steel processing plants, natural gas

plants, and sewage treatment systems. Natural sources include sulphurous hot springs and volcanic vents, swamps and bogs. Naturally-occurring sulphate-reducing bacteria can also produce H2S in domestic water systems. The processes which produce hydrogen sulphide often generate other sulphur-containing compounds, such as methyl mercaptan and dimethylsulphide. These substances are also highly malodorous, and are often grouped together with hydrogen sulphide and referred to as total reduced sulphur compounds, or TRS.

In the ambient air, the undesirable effects of H_2S are generally felt in terms of a bad odour. The odour threshold for H_2S is as low as 0.0001 ppm (0.1 ppb). At much higher concentrations (approximately 200 ppm) hydrogen sulphide affects the mucous membranes, causing eye and throat irritation. At 300 ppm, H_2S is immediately dangerous to life by causing paralysis of the lungs. High concentrations of hydrogen sulphide can also cause paint discoloration and metal corrosion, and are damaging to plants (Environment Canada, 1984; Masters, 1997). Life-threatening levels, in excess of 300 ppm, can exist in underground sewer pipe systems and occasionally above ground near sewer manholes, in situations where sewer gases are released from underground piping. During drilling for oil and gas, blow-outs can also occur with the release of large quantities of H_2S.

Ambient concentrations in New Brunswick, even in the vicinity of large emission sources, seldom exceed 40 ppb (0.04 ppm).

E. Ground-Level Ozone

Ozone (**O_3**) is a reactive, unstable form of oxygen. In very high concentrations, it is a bluish gas. The characteristic sharp smell of ozone may be recognised around electrical equipment such as motors or arc welders, where it is formed by the high temperature electric spark. In the concentrations found in outdoor air, even in the most severe pollution episodes, ozone is both colourless and odourless.

Ozone is not emitted directly from smokestacks and exhaust pipes, but is formed in the air from other pollutants, most importantly nitrogen oxides (NO_2) and hydrocarbons or VOCs (such as solvent and gasoline vapours).

Vehicle exhaust contains all the necessary compounds to produce ozone, and, as a result, cars and trucks are important contributors to ground level ozone concentrations. Industrial emissions of NO_x and hydrocarbons are also significant precursor emissions for ground level ozone.

Slow-moving air and strong sunshine greatly speed up the formation of ozone. As a result, ground level ozone is not typically a problem pollutant in the cooler months, but is likely to be more significant in hot, hazy summer weather. Such haze may build up over a period of days into a "**photochemical smog**". However, the yellow or brownish colour of such smog is usually due to nitrogen dioxide and fine chemical particles, not the ground level ozone itself.

Because the formation of ground level ozone depends on weather conditions, the severity of ozone pollution can be very variable from one year to the next. In New Brunswick, significant ozone episodes occur on average about six times per summer, mainly affecting the southern part of the province. Much of this ozone originates from populated regions of the north-eastern United States, especially the Washington to Boston "**corridor**".

Ground-level ozone irritates the lungs and can make breathing difficult. Exposure to high concentrations can result in chest tightness, coughing and wheezing. Recent health research suggests there is no threshold concentration below which ozone does not affect human health. Ground level ozone can cause damage to agricultural crops which are ozone-sensitive, such as potatoes and tomatoes. It can also cause noticeable leaf damage in other species. Forest trees and other vegetation may be injured, or growth inhibited. Ozone also weakens rubber, and attacks metals and painted surfaces (Bates, 1980; Multistakeholder NOx/VOC Science Program, 1997c).

Ozone levels are often lower in city centres than in surrounding rural areas. This is because ozone reacts with nitrogen oxides, often found in relatively high concentrations in city cores due to emissions from motor vehicles. This effect is seen in Saint John, although to a lesser extent than in larger cities. A separate network of sites exists to assess rural ozone. The results from that network are discussed later in this report.

F. Total Suspended Particulate

Particles in the air (also called "particulates" by air pollution scientists) may either be of natural origin or the result of human activity. Some common natural sources and types of particulates include wind-blown soil dust, forest fires, sea salt, volcanoes, and plants (which produce pollen and spores). Human activities which generate particles include fuel combustion (domestic and industrial) and any other burning (e.g. waste incineration or slash burning); travel on dirt roads, construction work, and mining and quarrying. Dust on road and work sites is often wetted down to control particulate emissions. Other kinds of particles from in the air when gasses such as sulphur dioxide (SO_2) and nitrogen oxides (NO_X) react together. These particles are partly responsible for the yellowish "smog" sometimes seen over large cities.

"Total suspended particulate" (**TSP**) has been a standard pollution measurement for many years, obtained by drawing a large volume of air through a special filter. This method makes no distinction between natural particles, such as pollen and spores, and particles which are emitted from vehicles or smokestacks.

People with existing breathing complaints such as asthma, **bronchitis** or **emphysema**, are liable to be adversely affected by high concentrations of particulates (Wilson and Spengler, 1996; CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1998).

Particulates can also cause corrosion and soiling of metalwork or other materials, damage vegetation, and reduce visibility.

G. Inhalable Particulate (PM_{10})

Particles smaller than 10 microns (a micron is a millionth of a metre, or a thousandth of a millimetre) are called PM_{10}, and are not filtered out of the air by the nose, throat and upper windpipe. As a result, these very small particles can enter the lungs where they may irritate or otherwise have an adverse effect on the delicate membranes and air sacs which absorb oxygen. Other toxic effects may occur, depending on the chemical make up of the fine particles. Because they can enter the lungs, PM_{10} particles are sometimes referred to as 'inhalable' particles, and are measured separately from TSP.

TERMS USED TO DESCRIBE PARTICLES AND HAZE

TSP: Total suspended particulates. A measure of particle concentration determined with a high-volume air sampler, which draws air through a filter over a 24-hour period. Includes particles with a wide range of sizes, up to 25-45 microns in diameter. TSP is normally measured on a nationally-standardised one-in-six day cycle.

PM_{10}: Particulate matter with an effective diameter of 10 microns or less. Also termed "inhalable particulates", as particles of this size are small enough to be inhaled via the mouth and some may enter the lungs.

$PM_{2.5}$: Particulate matter with an effective diameter of 2.5 microns or less, which bypass filtration in the nose and may be deposited in the lungs. Also referred to as "respirable" particulate.

COH: Coefficient of Haze. A relative measure of particle concentration determined by drawing air through a paper tape and measuring the change in light transmission of the tape.

Particles, particulates, aerosols: When referring to air quality, these terms are interchangeable, and refer to particles small enough to be transported some distance through the air. Most of these are less than 40 microns in diameter (roughly the size of pollen grains).

Fine particles: Particles with an effective diameter between 0.01 and 2 microns. Most particles forming as a result of industrial processes and combustion (natural or man made) are in this size range. Sometimes loosely used to refer to $PM_{2.5}$. Includes smoke particles.

Coarse particles: Particles with an effective diameter between 2 and 100 microns; includes PM_{10}. Much of the coarse particle load in the atmosphere is of natural (crustal) origin. Also includes pollen and spores.

F. Total Suspended Particulate

Particles in the air (also called "particulates" by air pollution scientists) may either be of natural origin or the result of human activity. Some common natural sources and types of particulates include wind-blown soil dust, forest fires, sea salt, volcanoes, and plants (which produce pollen and spores). Human activities which generate particles include fuel combustion (domestic and industrial) and any other burning (e.g. waste incineration or slash burning); travel on dirt roads, construction work, and mining and quarrying. Dust on road and work sites is often wetted down to control particulate emissions. Other kinds of particles from in the air when gasses such as sulphur dioxide (SO_2) and nitrogen oxides (NO_X) react together. These particles are partly responsible for the yellowish "smog" sometimes seen over large cities.

"Total suspended particulate" (**TSP**) has been a standard pollution measurement for many years, obtained by drawing a large volume of air through a special filter. This method makes no distinction between natural particles, such as pollen and spores, and particles which are emitted from vehicles or smokestacks.

People with existing breathing complaints such as asthma, **bronchitis** or **emphysema**, are liable to be adversely affected by high concentrations of particulates (Wilson and Spengler, 1996; CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1998).

Particulates can also cause corrosion and soiling of metalwork or other materials, damage vegetation, and reduce visibility.

G. Inhalable Particulate (PM_{10})

Particles smaller than 10 microns (a micron is a millionth of a metre, or a thousandth of a millimetre) are called PM_{10}, and are not filtered out of the air by the nose, throat and upper windpipe. As a result, these very small particles can enter the lungs where they may irritate or otherwise have an adverse effect on the delicate membranes and air sacs which absorb oxygen. Other toxic effects may occur, depending on the chemical make up of the fine particles. Because they can enter the lungs, PM_{10} particles are sometimes referred to as 'inhalable' particles, and are measured separately from TSP.

TERMS USED TO DESCRIBE PARTICLES AND HAZE

TSP: Total suspended particulates. A measure of particle concentration determined with a high-volume air sampler, which draws air through a filter over a 24-hour period. Includes particles with a wide range of sizes, up to 25-45 microns in diameter. TSP is normally measured on a nationally-standardised one-in-six day cycle.

PM_{10}: Particulate matter with an effective diameter of 10 microns or less. Also termed "inhalable particulates", as particles of this size are small enough to be inhaled via the mouth and some may enter the lungs.

$PM_{2.5}$: Particulate matter with an effective diameter of 2.5 microns or less, which bypass filtration in the nose and may be deposited in the lungs. Also referred to as "respirable" particulate.

COH: Coefficient of Haze. A relative measure of particle concentration determined by drawing air through a paper tape and measuring the change in light transmission of the tape.

Particles, particulates, aerosols: When referring to air quality, these terms are interchangeable, and refer to particles small enough to be transported some distance through the air. Most of these are less than 40 microns in diameter (roughly the size of pollen grains).

Fine particles: Particles with an effective diameter between 0.01 and 2 microns. Most particles forming as a result of industrial processes and combustion (natural or man made) are in this size range. Sometimes loosely used to refer to $PM_{2.5}$. Includes smoke particles.

Coarse particles: Particles with an effective diameter between 2 and 100 microns; includes PM_{10}. Much of the coarse particle load in the atmosphere is of natural (crustal) origin. Also includes pollen and spores.

A number of recently published health studies have concluded that lung function, cardio-respiratory mortality, respiratory illness-related hospital admissions, and a variety of other health factors are related to ambient concentrations of PM_{10}. However, which particular aspect of the fine particles is causing these effects has not yet been fully resolved. Particle chemistry, and possibly acidity, may be important. As for ozone, there appears to be no lower concentration threshold below which health effects are not observed. Recent studies also suggest that particles have effects on the immune system (Wilson and Spengler, 1996; Blomberg, 1998).

In Canada, only the Greater Vancouver Regional District (GVRD) and the province of Newfoundland have a standard in place for PM_{10}, although work on developing a national objective is currently under way. In the United States, standards exist both nationally and in California, which has the same standard as the GVRD (see table on page 5).

Another standard specification for measuring particulates is $PM_{2.5}$, which refers to particles equal to or smaller than 2.5 microns in size. These particles are thought to be of special significance in terms of health impacts, as they have a higher chance of entering and remaining in the lungs if inhaled, compared to PM_{10} or larger particles. They are sometimes referred to as 'respirable particles'.

TSP data provide no direct estimate of fine, **inhalable particles**. This, plus the fact that high volume samplers are not designed for continuous operation, are significant drawbacks from the point of view of air quality assessment. New particle monitoring technologies have been introduced in recent years which address these concerns.

An example is the **TEOM** monitor. These units provide continuous, unattended recording and electronic logging and reporting functions. Since 1995, **NBDOE** has purchased and installed several of these devices. Two were installed in Saint John (at the Forest Hills monitoring site) towards the end of 1996, one measuring PM_{10} and the other $PM_{2.5}$.

In April 1998 an additional TEOM unit was established in St Andrews to monitor trans-boundary $PM_{2.5}$. Further units were set up in Fredericton, Bathurst and Moncton during 1999.

7. MONITORING NETWORKS

Compliance with air quality objectives or regulatory standards is determined by monitoring. Because exposure to many air pollutants can occur at any time, most are monitored continuously, although particulates have been an exception. However, new technology now allows continuous measurement. As a result, continuous particulate measurements are gradually becoming more widespread and available.

Monitoring locations are selected so that they will provide information which is representative of the surrounding area. In cases where there is a known pollutant source, monitors are often distributed around it in locations where the impact is expected to be greatest. Such locations are typically selected based on the results of computer dispersion models. These are computer programs which simulate the behaviour of plumes, or discharge streams of gases as they are released from smokestacks. Such models take into account the complete variety of weather conditions which may be experienced in the area where the stack is located, as well as the nature of the local landscape.

In New Brunswick, large industrial emission sources, such as electricity generating stations or pulp mills, are legally required by NBDOE to carry out ambient air quality monitoring as prescribed in their Approvals to Operate. Such Approval conditions also detail the required equipment specifications, locations and reporting frequency. In such cases, the monitoring equipment and maintenance procedures are checked periodically by NBDOE staff or independent auditors, to ensure the required standards for operation and technical accuracy are being met.

In the case of air pollutants which are transported long distances, and which may be found in rural, as well as urban areas, NBDOE establishes and operates its own monitoring sites. The Department also maintains sites in areas where there are multiple large industrial emission sources, such as Greater Saint John. In addition to 13 provincial sites, there is one federally-operated acid rain monitoring site in New Brunswick (at Harcourt, in eastern New Brunswick). Federal support is also provided for the operation of several other monitoring sites in Saint John, Moncton and St. Andrews.

The location of air quality monitoring sites and the main regional and local networks are shown on the following map (Figure 1). More detail on the exact location of each site is provided in the following sections.



Figure 1. Locations of air quality monitoring sites in New Brunswick. The major industry or urban networks are identified. Filled circles on the map indicate rural ozone sites. The remainder indicate ambient monitoring locations for other substances including sulphur dioxide, nitrogen dioxide and particulates.

8. AIR QUALITY MONITORING RESULTS FOR 1998

This report contains information for 1998. Results are presented for each monitoring network in the Province. The locations of the monitoring sites are shown on regional scale maps. The numeric results are shown in tables, and further details in chart form appear in Appendix III.

Explanatory notes are provided on each network, and a discussion of the results for each network is included.

A. SAINT JOHN

The Saint John area has the longest history of air quality monitoring in New Brunswick, beginning in 1961 (see box on pages 1-2). Since that time, air quality has been monitored at more than 30 different locations in the city and surrounding area. Air quality monitoring sites which are presently active (a total of 12 separate locations) are shown on the following map (Figure 2).



Figure 2. Air quality monitoring sites in Saint John, New Brunswick.

Most of these sites are electronically linked to a central computer at the NBDOE regional office in Saint John. This system communicates with the monitors a minimum of once each hour and obtains the latest readings. These are then added to the existing data archive and are used to prepare IQUA Public Information messages, as well as to determine the nature of any abatement actions required by industries if concentrations rise above pre-determined trigger points. Such episode control systems are specified in various Approvals to Operate issued to major emission sources by the Department.

On the City's west side, three monitoring sites for hydrogen sulphide are operated by Irving Pulp and Paper Ltd. NBDOE also operates a site at the Hillcrest Baptist Church off Lancaster Avenue, at which sulphur dioxide, hydrogen sulphide and PM_{10} are monitored, and another site on Manawagonish Road, for PM_{10} only. In east Saint John, three sites for sulphur dioxide are operated by Irving Oil Ltd, as required by the company's operating approval, and results are sent electronically to the Department's data system.

NBDOE also maintains sites at Forest Hills and Champlain Heights in the eastern suburbs, and at the Customs and Provincial buildings in the downtown area. The Customs site has monitors for ozone, sulphur dioxide, nitrogen dioxide, carbon monoxide and coefficient of haze (a measure of particulate). At Forest Hills there are monitors for ozone, sulphur dioxide, nitrogen oxides, coefficient of haze, PM_{10}, $PM_{2.5}$ and volatile organic compounds. The Champlain Heights site monitors sulphur dioxide only.

A.1 Carbon Monoxide

This pollutant is monitored at the Customs Building site to provide data representative of the city centre. Peak hourly values in every month were well below the applicable standard of 30 ppm in 1998. There were also no exceedances of the 8-hour standard of 13 ppm.

A.2 Nitrogen Dioxide

There were no exceedances of the 1-hour standard of 210 ppb at either the Forest Hills or Customs Building monitoring sites in 1998 . Neither were the 24-hour standard (105 ppb) or the annual standard (52 ppb) exceeded. Nitrogen dioxide levels at the Customs site tended to be somewhat higher than those at Forest Hills, although still well within the applicable standards at all times.

A.3 Sulphur Dioxide

There were no exceedances of the annual average standard of 11 ppb at any of the seven monitoring sites in 1998. A number of exceedances of the 1-hour and 24-hour standards occurred during 1998. These are summarised by site in the following tables.

Exceedances of the 1-hour sulphur dioxide standard in 1998 Saint John (number of hours)													
Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Forest Hills	0	2	0	M	0	2	1	0	0	0	0	0	5
Champlain Heights	0	2	2	0	0	0	0	0	0	0	0	0	4
Hillcrest	0	0	0	0	0	0	0	0	0	0	0	0	0
Customs	0	3	0	0	0	0	0	0	0	0	0	0	3
Three Mile	0	0	0	0	0	0	0	0	0	0	0	0	0
Forest Products	2	0	0	2	5	4	0	1	6	0	2	0	11
Silver Falls	0	0	0	0	0	0	1	0	0	0	0	0	1
Total	2	7	2	2	0	0	3	2	6	0	0	0	24

M= missing data. The 1 hour standard is 17 pphm, which is equivalent to 170 ppb.

Exceedances of the 24-hour sulphur dioxide standard in 1998 Saint John (number of hours)													
Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Forest Hills	0	0	0	M	0	0	4	5	0	0	0	0	9
Champlain Heights	0	0	10	0	4	0	0	0	0	0	12	0	26
Hillcrest	0	0	0	0	0	0	0	0	0	0	0	0	0
Customs	0	31	0	0	0	0	0	0	0	0	0	0	31
Three Mile	0	0	0	0	0	0	0	0	0	0	0	0	0
Forest Products	43	0	21	0	0	0	0	0	7	32	10	6	119
Silver Falls	0	0	0	0	0	0	0	0	0	0	0	0	0
Total	43	31	31	0	4	0	4	5	7	32	22	6	185

M= missing data. The 24-hour standard is 6 pphm, which is equivalent to 60 ppb.

Tables of Exceedances - What they Mean

The numbers in the tables of exceedances show the number of occasions when readings were above the standard. For example, the one standard for sulphur dioxide in Saint John is 170 ppb. Any hourly period when the measured value was higher than 170 ppb counts as one exceedance of that hourly standard. A 31-day month has 31 x 24 = 744 hours, so the maximum possible number of hourly exceedances for the month would be 744. If that happened, compliance would be 0%. Conversely, with no exceedances, compliance would be 100%.

Considering Forest Products sites in January, 1998, 2 individual hours out of 744 were logged exceeding the 170 ppb level. Compliance for the month was 742 out of 744 hours, or 99.73%.

Where 24-hour standards exist (as for SO_2 and H_2S), compliance is calculated using a running 24 hour average. In other words, not just individual 24 hour calendar days are considered, but every possible 24 hour period in each month, e.g. the 24 hours ending at 10 am on the 5th, the 24 hour period ending at 11 am on the 5th, and so on for the whole period in question. Each hour, the 24 hour average is recalculated.

Any hour that the calculation is made and the result is over the 24-hour standard, counts as an exceedance. There could be up to 744 exceedances in a 31-day month. Because a 24-hour average tends to rise and fall gradually, compared to an hourly reading, the total number of 24-hour exceedances is almost always greater than the number of 1-hour exceedances.

Saint John is an industrial city with several major emission sources close to its centre. In spite of this, and the fact that local sulphur dioxide standards were made twice as stringent as the National Objectives in 1995, compliance was 100% at two of the seven monitored locations during 1998. Although the goal of full compliance has yet to be fully attained in the case of sulphur dioxide in parts of Saint John, the present system of air quality management is considered to be working well.

Compliance with sulphur dioxide standards during 1998 at the remaining five sites, expressed as a percentage of all hours, ranged from 99.87% to 99.99% for the 1-hour standard, and from 98.64% to 99.90% for the 24-hour standard.

A.3.1 Sulphur Dioxide Episode Control

An episode control program is in place to prevent ambient sulphur dioxide reaching undesirably high levels in Saint John. Control actions are initiated by major industries in the city in response to measurements made at the fixed monitoring sites.

As noted earlier, these control actions are made mandatory by being incorporated into the relevant Approvals to Operate issued by NBDOE. The episode control plans themselves are subject to continual review. NBDOE meets regularly (at least 6 to 8 times per year) with staff of the major industries in the city to review compliance in respect of sulphur dioxide.

All exceedance events are examined in detail and any shortfalls in the nature and extent of response action are addressed. NBDOE staff sometimes request emission control actions separate from or in addition to those specified in the response plans. Such action may be warranted due to unusual conditions, such as poor dispersion, or during periods when smog advisories are in effect.

Some of the ways in which industries respond to rising levels of sulphur dioxide include switching to lower or near-zero sulphur fuels, and reducing production rates or electricity generating rate. Response action is begun when monitored concentrations reach approximately half the 1-hour standard of 17 parts per hundred million (i.e. at 8 pphm).

Tables of Exceedances - What they Mean

The numbers in the tables of exceedances show the number of occasions when readings were above the standard. For example, the one standard for sulphur dioxide in Saint John is 170 ppb. Any hourly period when the measured value was higher than 170 ppb counts as one exceedance of that hourly standard. A 31-day month has 31 x 24 = 744 hours, so the maximum possible number of hourly exceedances for the month would be 744. If that happened, compliance would be 0%. Conversely, with no exceedances, compliance would be 100%.

Considering Forest Products sites in January, 1998, 2 individual hours out of 744 were logged exceeding the 170 ppb level. Compliance for the month was 742 out of 744 hours, or 99.73%.

Where 24-hour standards exist (as for SO_2 and H_2S), compliance is calculated using a running 24 hour average. In other words, not just individual 24 hour calendar days are considered, but every possible 24 hour period in each month, e.g. the 24 hours ending at 10 am on the 5th, the 24 hour period ending at 11 am on the 5th, and so on for the whole period in question. Each hour, the 24 hour average is recalculated.

Any hour that the calculation is made and the result is over the 24-hour standard, counts as an exceedance. There could be up to 744 exceedances in a 31-day month. Because a 24-hour average tends to rise and fall gradually, compared to an hourly reading, the total number of 24-hour exceedances is almost always greater than the number of 1-hour exceedances.

Saint John is an industrial city with several major emission sources close to its centre. In spite of this, and the fact that local sulphur dioxide standards were made twice as stringent as the National Objectives in 1995, compliance was 100% at two of the seven monitored locations during 1998. Although the goal of full compliance has yet to be fully attained in the case of sulphur dioxide in parts of Saint John, the present system of air quality management is considered to be working well.

Compliance with sulphur dioxide standards during 1998 at the remaining five sites, expressed as a percentage of all hours, ranged from 99.87% to 99.99% for the 1-hour standard, and from 98.64% to 99.90% for the 24-hour standard.

A.3.1 Sulphur Dioxide Episode Control

An episode control program is in place to prevent ambient sulphur dioxide reaching undesirably high levels in Saint John. Control actions are initiated by major industries in the city in response to measurements made at the fixed monitoring sites.

As noted earlier, these control actions are made mandatory by being incorporated into the relevant Approvals to Operate issued by NBDOE. The episode control plans themselves are subject to continual review. NBDOE meets regularly (at least 6 to 8 times per year) with staff of the major industries in the city to review compliance in respect of sulphur dioxide.

All exceedance events are examined in detail and any shortfalls in the nature and extent of response action are addressed. NBDOE staff sometimes request emission control actions separate from or in addition to those specified in the response plans. Such action may be warranted due to unusual conditions, such as poor dispersion, or during periods when smog advisories are in effect.

Some of the ways in which industries respond to rising levels of sulphur dioxide include switching to lower or near-zero sulphur fuels, and reducing production rates or electricity generating rate. Response action is begun when monitored concentrations reach approximately half the 1-hour standard of 17 parts per hundred million (i.e. at 8 pphm).

A.4 Ground Level Ozone

Ozone was monitored at three sites in the city during 1998: Forest Hills, the Customs Building and in west Saint John at Hillcrest Church. During 1998 there were 8 exceedances of the 1-hour National Ambient Air Quality Objective for ozone of 82 ppb in the Saint John Network, all recorded during an episode in May at the Hillcrest site in west Saint John. As noted earlier, this objective is employed only as a guideline for purposes of evaluation. There are no standards presently in effect for ground level ozone in New Brunswick. Further details follow in section 9, where complete results for all ozone monitoring sites are summarised.

As noted previously, ozone is an air pollutant which can travel long distances, especially when winds carry the ozone over water (an example is transport from the Boston area to New Brunswick over the Gulf of Maine and Bay of Fundy). Years of monitoring, **modelling** and **trajectory analysis** have shown that the vast majority of ground level ozone observed in New Brunswick originates in the north-eastern United States.

A.5 Total Suspended Particulate

TSP is measured at the Forest Hills and Provincial Building sites. This measurement of particulate is receiving reduced attention both across North America, and world-wide, as more focus is placed on measurements of fine particulates such as data for PM_{10} and $PM_{2.5}$. Nevertheless, Canadian and New Brunswick standards still exist for TSP at present.

TSP measurements are made once every six days on a nationally standardised timetable. Each high volume sampler used to monitor TSP runs for a full 24 hours every sixth day.

As in 1997, the 24-hour standard of 120 micrograms per cubic metre was met on every measured day at the Provincial Building and Forest Hills sites during 1998. The annual **geometric mean** was well below the standard of 70 micrograms per cubic metre at both sites in both years.

Because of the design of high volume samplers, TSP results are influenced by particles such as road dust as well as natural particles such as pollen grains. High levels in spring and fall are often the result of wind-blown dust from roadsides. In winter, results are sometimes influenced by high concentrations of smoke particles from woodburning appliances.

A.6 Inhalable Particulate (PM_{10})

NBDOE operates high volume samplers at 4 sites in Saint John (Forest Hills, Provincial Building, Hillcrest and Western District Police) which are specially modified to provide data on PM_{10}. As noted earlier, there is no Canadian National Objective presently in place for PM_{10}, and no provincial standard in New Brunswick. For evaluation purposes, reference is made to the standards in place in Greater Vancouver, the United States, and the State of California (page 5).

Compliance with these standards at sites in Saint John in 1998 was broadly similar to that for TSP. The California/GVRD 24-hour standard of 50 micrograms per cubic metre was exceeded twice at the Hillcrest site, and three times at the Provincial Building during 1998.

A.7 Hydrogen Sulphide

This air pollutant is monitored at the Hillcrest site (NBDOE) as well as three sites operated by Irving Pulp and Paper (Milford, Indian Town and Sherbrooke St.)

There were a number of exceedances at these sites in 1998, as indicated in the following table. As a percentage of total hours, compliance ranged from 99.67% to 99.82% for the 1-hour standard and 96.84% to 98.45% for the 24-hour standard.

Exceedances of standards for Hydrogen Sulphide in 1998
Saint John (number of hours)

1-hour standard (11 ppb)

Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Hillcrest	1	0	M	0	0	1	1	0	14	0	0	0	17
Sherbrooke	0	2	3	0	0	0	0	0	1	0	0	12	16
Milford	0	0	10	0	0	0	1	0	2	0	0	10	23
Indian Town	10	3	2	0	0	0	0	3	1	0	0	10	29
Total	11	3	15	0	0	1	2	3	18	0	0	32	85

24-hour standard (3.5 ppb)

Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Hillcrest	29	0	M	0	0	0	0	8	221	0	0	0	258
Sherbrooke	7	0	24	0	0	0	0	24	0	10	0	92	157
Milford	0	0	39	0	0	11	0	0	21	0	0	65	136
Indian Town	80	58	25	0	0	0	0	0	39	0	0	75	277
Total	116	58	88	0	0	11	0	32	281	10	0	232	828

M= missing data.

A.8 Index of the Quality of the Air (IQUA)

The IQUA system has been used in Saint John for 20 years to help make air quality monitoring results easier to understand. Results for each pollutant measurement are expressed on a scale from 1-100, and classed as "good" (index 0 to 25), "fair" (26 to 50), "poor" (51 to 100) or "very poor" (over 100). Each of the categories is based on the National Air Quality Objectives listed in Appendix II. For example, "good" air quality indicates that pollutants are in the "desirable" range as defined by the air quality objectives. Values in the "fair" range are above the desirable, but below the acceptable objective. IQUA information is distributed daily via the NBDOE web site:
http://www.gov.nb.ca/scripts/environm/air/GetValues.idc

This web page is updated three times per day. IQUA information is also accessible by phone via recorded message (dial 636 4991 in the Saint John area). The recorded message is updated hourly.

For each hour, the IQUA index is computed for each pollutant measured at the site. The value reported is the highest of each of the individual values. For example if two pollutants are in the "good" range and one is in the "poor" range, then the index for the hour would be

The IQUA System

National Air Quality Objective		**IQUA Level**
Exceeds Maximum Tolerable	VERY POOR	100 or more
Exceeds Maximum Acceptable	POOR	51 - 100
Exceeds Maximum Desirable	FAIR	26 - 50
Lower than Maximum Desirable	GOOD	0 - 25

reported as "poor". In addition, the pollutant responsible for determining the overall index value is usually identified.

Summary statistics are given here for the three designated IQUA sites in Saint John: Customs Building (downtown), Forest Hills (east) and Hillcrest (west). The charts show the number of hours logged in each IQUA category. It is apparent that the vast majority of the time, air quality was in the "good" category during 1998 (from 94 to more than 99% of the time). The percentage of hours in the "fair" range varied from almost zero at Forest Hills to 6% at the Hillcrest site in West Saint John, the Downtown Customs location having an intermediate 3.5%. The percentage in the "poor" category was even lower: less than 1% at all three sites, with a maximum frequency of 0.5% at Hillcrest, West Saint John.



Figure 3. Air quality index summary for 1998: Customs Building, Saint John.



Figure 4. Air Quality Index summary for 1998: Forest Hills, Saint John.



Figure 5. Air Quality Index summary for 1998: Hillcrest, Saint John.

B. MIRAMICHI

There are two monitoring sub-networks in the Miramichi region, one centred on the REPAP pulp mill emission sources, and the other on NB Power's Millbank gas turbine generating site. Pollutants of concern in these networks include hydrogen sulphide and particulates (REPAP) plus nitrogen dioxide and sulphur dioxide (Millbank). Figure 6 shows the locations of the five sites in the region.



Figure 6. Air quality monitoring sites in the Miramichi region.

B.1 REPAP NETWORK

B.1.1 Hydrogen Sulphide

Based on measurements for hydrogen sulphide at the Groundwood and King George Highway sites, the compliance summary for 1998 is as follows:

Exceedances of standards for Hydrogen Sulphide in 1998
REPAP sites (number of hours)

1-hour standard (11 ppb)													
Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Groundwood	0	1	0	1	0	0	0	6	0	0	1	0	9
KG Highway	23	36	44	41	31	24	90	77	41	23	0	3	410
Total	23	37	44	42	31	24	90	83	41	23	1	3	419
24-hour standard (3.5 ppb)													
Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Groundwood	0	0	0	0	0	0	0	25	0	0	0	0	25
KG Highway	88	88	194	121	123	108	383	247	185	99	0	0	1636
Total	88	88	194	121	123	108	383	272	185	99	0	0	1661

M = missing data

Exceedances: why they occur

Exceedances of air quality standards can occur for several reasons. For substances such as hydrogen sulphide, sulphur dioxide, nitrogen oxides, carbon monoxide and TSP, local emissions dominate. Exceedances for these contaminants may be due to emissions which are higher than usual, often together with unusual weather conditions. For example, winds blowing directly from an emission source (such as a smokestack) towards a monitoring site, or conditions when pollutants cannot disperse easily.

In the case of ozone, local emissions are far less important, and exceedances are dependent on weather patterns. Exceedances occur when winds bring ozone into New Brunswick from polluted regions beyond our borders (typically the northeastern US).

Exceedances of TSP often occur due to dust raised by the wind from roads. This often happens in April and May when surfaces dry out and roads and paths are still covered with fine sand from winter applications.

While compliance at the Groundwood site was good, a significant number of exceedances occurred at the King George Highway site. Compliance was attained for 95.3% of all hours (1-hour standard) and 81.32% of hours (24-hour standard). For the 1-hour standard, these results are similar to those obtained in 1996 and 1997. For the 24-hour standard, the 1998 data represent an improvement in compliance of about 5%.

Work has been ongoing at the REPAP mill complex since 1995 aimed at reducing ambient levels of hydrogen sulphide in the vicinity. A condensate stripper was installed in December 1998, which is expected to reduce the amount of sulphur compounds in the wastewater before it is discharged to the lagoon. This is expected to bring about an improvement in ambient air quality. Monitoring results will be reviewed during 1999 to assess progress.

B.1.2 Total Suspended Particulate

There were no exceedances of the TSP standard at any of the three monitoring sites during 1998. Detailed results are shown in Appendix III.

B.1 REPAP NETWORK
B.1.1 Hydrogen Sulphide

Based on measurements for hydrogen sulphide at the Groundwood and King George Highway sites, the compliance summary for 1998 is as follows:

Exceedances of standards for Hydrogen Sulphide in 1998
REPAP sites (number of hours)

1-hour standard (11 ppb)

Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Groundwood	0	1	0	1	0	0	0	6	0	0	1	0	9
KG Highway	23	36	44	41	31	24	90	77	41	23	0	3	410
Total	23	37	44	42	31	24	90	83	41	23	1	3	419

24-hour standard (3.5 ppb)

Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Groundwood	0	0	0	0	0	0	0	25	0	0	0	0	25
KG Highway	88	88	194	121	123	108	383	247	185	99	0	0	1636
Total	88	88	194	121	123	108	383	272	185	99	0	0	1661

M = missing data

Exceedances: why they occur

Exceedances of air quality standards can occur for several reasons. For substances such as hydrogen sulphide, sulphur dioxide, nitrogen oxides, carbon monoxide and TSP, local emissions dominate. Exceedances for these contaminants may be due to emissions which are higher than usual, often together with unusual weather conditions. For example, winds blowing directly from an emission source (such as a smokestack) towards a monitoring site, or conditions when pollutants cannot disperse easily.

In the case of ozone, local emissions are far less important, and exceedances are dependent on weather patterns. Exceedances occur when winds bring ozone into New Brunswick from polluted regions beyond our borders (typically the northeastern US).

Exceedances of TSP often occur due to dust raised by the wind from roads. This often happens in April and May when surfaces dry out and roads and paths are still covered with fine sand from winter applications.

While compliance at the Groundwood site was good, a significant number of exceedances occurred at the King George Highway site. Compliance was attained for 95.3% of all hours (1-hour standard) and 81.32% of hours (24-hour standard). For the 1-hour standard, these results are similar to those obtained in 1996 and 1997. For the 24-hour standard, the 1998 data represent an improvement in compliance of about 5%.

Work has been ongoing at the REPAP mill complex since 1995 aimed at reducing ambient levels of hydrogen sulphide in the vicinity. A condensate stripper was installed in December 1998, which is expected to reduce the amount of sulphur compounds in the wastewater before it is discharged to the lagoon. This is expected to bring about an improvement in ambient air quality. Monitoring results will be reviewed during 1999 to assess progress.

B.1.2 Total Suspended Particulate

There were no exceedances of the TSP standard at any of the three monitoring sites during 1998. Detailed results are shown in Appendix III.

B.2 MILLBANK NETWORK

The two sites at Millbank (Rockcliff and Lower Newcastle, see Figure 6) are positioned to assess the impact of NB Power's gas turbine generating station. The pollutants monitored include sulphur dioxide, nitrogen dioxide and TSP.

B.2.1 Nitrogen dioxide

There were no exceedances of the 1-hour or 24-hour standards at either monitoring site in either 1998, and monthly means were all very low. Monthly results for 1998 are shown in Appendix III.

B.2.2 Sulphur dioxide

As for nitrogen dioxide, in 1998 there were no exceedances of the 1-hour or 24-hour standards at either monitoring site, and the monthly means were also all very low. This is both a reflection of the relatively infrequent operation of the Millbank plant, and the low sulphur fuel it uses. Monthly results are shown in Appendix III.

B.2.3 Total Suspended Particulate

None of the measurements made exceeded the 24-hour standard of 120 micrograms per cubic metre in 1998, and almost all were well below this value. All individual results are given in Appendix III.

C. GRAND LAKE - NB POWER

Figure 7 shows the locations of the four monitoring sites in this network. These are sited to monitor the effects of the Grand Lake coal-fired electrical generating station and associated activities. The four monitoring sites are operated by NB Power and each measures sulphur dioxide and TSP.



Figure 7. Air quality monitoring sites in the Grand Lake Network.

C.1 Sulphur dioxide

Compliance was very good at all sites in 1998. There were a small number of exceedances at the Newcastle Centre and Cox Point sites, as follows:

Exceedances of the 1-hour sulphur dioxide standard in 1998 NB Power Grand Lake (number of hours)													
Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Flowers Cove	0	0	0	0	0	0	0	0	0	0	0	0	0
Newcastle Centre	0	0	0	0	1	0	0	1	0	1	0	0	3
Bailey Point	0	0	0	0	0	0	0	0	0	0	0	0	0
Cox Point	0	0	0	0	1	0	0	0	0	0	0	0	1
Total	0	0	0	0	2	0	0	1	0	1	0	0	4

M= missing data. The 1 hour standard is 34 pphm or 340 ppb.

The three exceedances at the Newcastle Centre site represents 99.96% compliance for the year. There were no exceedances of the 24-hour standard of 11 pphm (110 ppb) at any of the four sites in 1998.

C.2 Total Suspended Particulate

In 1998, all the results were well below the 24-hour standard of 120 micrograms per cubic metre. Complete results are given in Appendix III.

D. EDMUNDSTON - FRASER INC.

Figure 8 shows the locations of the two monitoring sites in the region (Cormier and Sacred Heart), located primarily to monitor the impacts of the Fraser Inc. pulp mill. At each site, sulphur dioxide and TSP are monitored.



Figure 8. Air quality monitoring sites in the Edmundston network.

D.1 Sulphur Dioxide

There were no exceedances of the 1-hour or 24-hour standards at either monitoring site during 1998.

D.2 Total Suspended Particulate

There were 14 days on which the 24-hour standard of 120 micrograms per cubic metre was exceeded at the Cormier site, and no exceedances at the Sacred Heart site.

The Cormier location is close to the main entrance to the Fraser mill, and is affected by road dust from heavy traffic entering the facility. High TSP values generally occur in spring, when pulverised sand from winter road treatment is drying out and is raised by the wind.

Detailed results are shown in Appendix III.

E. BELLEDUNE

There are a number of monitoring sites in the Belledune region. Four of these are located for the assessment of emissions from the Brunswick Mining and Smelting complex. A further five monitors are operated for the assessment of NB Power's coal-fired electrical generating station.

Figure 9 shows the locations of all the monitoring sites in the region.



Figure 9. Air quality monitoring sites in the Belledune Network.

E.1. BRUNSWICK MINING AND SMELTING

All sites in the Brunswick Mining and Smelting network monitor sulphur dioxide, and three also measure TSP.

E.1.1 Sulphur dioxide

In 1998 there was a small number of exceedances of the 1-hour standard, as summarised below. The 1 hour standard is 34 pphm or 340 ppb.

There were exceedances of the 24-hour standard (11.5 pphm or 115 ppb) in April at one site.

Exceedances of the 1-hour sulphur dioxide standard in 1998
Brunswick Mining and Smelting, Belledune (number of hours)

Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Airstrip	0	0	0	2	2	0	0	0	0	0	0	0	4
Chalmers	2	0	0	4	1	0	0	0	0	0	0	0	7
Townsite	0	1	0	0	0	1	0	0	0	0	0	0	2
Boulay	0	0	0	0	0	1	1	0	1	1	0	0	4
Total	2	1	0	6	3	2	1	0	1	1	0	0	17

Exceedances of the 24-hour sulphur dioxide standard in 1998
Brunswick Mining and Smelting, Belledune (number of hours)

Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Airstrip	0	0	0	12	0	0	0	0	0	0	0	0	12
Chalmers	0	0	0	0	0	0	0	0	0	0	0	0	0
Townsite	0	0	0	0	0	0	0	0	0	0	0	0	0
Boulay	0	0	0	0	0	0	0	0	0	0	0	0	0
Total	0	0	0	0	0	0	0	0	0	0	0	0	12

Percentage compliance ranged between 99.98% and 99.92% for the 1-h standard in 1998. Corresponding results for the 24-h standard were 100% and 99.86%.

Major work was carried out at the smelter complex in the summer of 1996, which has significantly reduced sulphur dioxide emissions. Further upgrades took place in 1997 including replacement of the acid plant catalyst system.

E.1.2 Total Suspended Particulate

There were no exceedances of TSP standards in this network during 1998. Complete results are given in Appendix III.

E.2 NB POWER

There are five sites in this network, all of which monitor for sulphur dioxide. Two sites also monitor nitrogen dioxide.

E.2.1 Sulphur dioxide

Compliance was very good in this network. There was only a small number of exceedances, as summarised below.

Exceedances of the 1-hour sulphur dioxide standard in 1998 NB Power Network, Belledune (number of hours)													
Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Madran	0	0	0	0	0	0	0	0	0	0	0	0	0
Pointe Verte	0	0	0	0	0	0	0	0	0	0	0	0	0
Belledune E	2	1	0	1	0	0	0	0	0	0	0	0	4
Jacquet River	0	0	0	0	0	0	0	0	0	0	0	0	0
Municipal Hall	0	0	0	0	0	0	0	0	0	0	0	0	0
Total	2	1	0	1	0	0	0	0	0	0	0	0	4

The 1 hour standard is 34 pphm or 340 ppb.

In 1998 there were no exceedances of the 24-hour standard of 11 pphm at any site.

E.2.2 Nitrogen dioxide

This contaminant is measured at Belledune East and Municipal Hall. There were no exceedances of the applicable 1 or 24-hour standards in 1998 at either location.

F. DALHOUSIE - NB POWER

Figure 10 shows the locations of the sites in the region. The sites in this region are operated to monitor the effects of the NB Power Dalhousie electrical generating station. Eight sites measure sulphur dioxide; one of the eight also monitors for TSP, and there is one additional TSP site (9 sites in all). Because of potential pollution transport across the Bay of Chaleur, three of the eight stations are located in the province of Québec.



Figure 10. Air quality monitoring sites in the Dalhousie Network.

F.1 Sulphur dioxide

Compliance with the applicable 1-hour and 24-hour standards was 100% at all sites in 1998. Concentrations were notably low; the peak 1-hour reading in the network was 138 ppb, which is less than half the standard. Monthly average concentrations were also very low as can be seen in Appendix III.

F.2 Total Suspended Particulate

TSP was measured at the Coal Berm and Dalhousie Tower sites. Results are shown in Appendix III. None of the individual readings obtained were above the 24-hour standard of 120 micrograms per cubic metre in 1998, and the annual geometric means were also well below the standard of 70 micrograms per cubic metre.

G. FREDERICTON

G.1 Total Suspended Particulate

In Fredericton, the only air quality monitoring site operating in 1998 was for TSP. The monitoring site is at the fire hall on the corner of York and Dundonald streets. There were two readings in 1998 which exceeded the 24-hour standard of 120 micrograms per cubic metre.

H. MONCTON

The Moncton air quality monitoring site was established in July, 1998 and is situated at the Highfield Street water pumping station. The site location was chosen to provide readings representative of the central city suburbs, in areas which may be influenced by emissions from vehicles or institutional heating systems, as well as regional pollutants such as ozone.

H.1 Carbon monoxide

No exceedances of hourly or 8-hourly standards for carbon monoxide occurred from July to December. Readings were similar to those recorded in downtown Saint John, the only other location in the province where carbon monoxide is measured.

H.2. Nitrogen dioxide

No exceedances of hourly or 24-hourly standards for nitrogen dioxide occurred from July to December.

H.3 Ozone

There were two exceedances of the hourly objective for ozone in July 1998. More discussion of ozone data may be found in section 9.

H.4 Index of the Quality of the Air

Hourly IQUA reports are generated for the Moncton site and made available via recorded message at 851 6610. Summary statistics for the period of operation of this site during 1998 (July-December) are shown in the following figure. The results show that the Moncton data were in the good category for more than 98% of the time.

Figure 11. Air Quality Index Summary 1998: Moncton.

9. RURAL OZONE NETWORK - SOUTHERN NEW BRUNSWICK

Figure 12 shows the locations of the sites which monitor ground level ozone in southern New Brunswick. This network is operated to assess the impact of long-range transported ozone. It focuses on the southern portion of the province, which is the region most affected by **long range transport**, as shown by special short-term monitoring studies and **trajectory analyses** (e.g. Fuentes and Dann, 1994; Tordon et al., 1994; Multistakeholder NOx/VOC Science Program, 1997a, 1997b).



Figure 12. Locations of ozone monitoring sites in New Brunswick (1998).

In 1998, exceedances of the one-hour national objective of 82 ppb occurred at seven different sites, but the total number of exceedances was small. The exceedance summary is given in the following table. In 1998 there were four out of eleven sites with no exceedances, compared to five out of nine in 1997. The frequency of ozone exceedances was higher in 1998 than 1997, when adjusted for the number of sites in operation. However, the number of hours of exceedance is quite variable from year to year, being heavily influenced by the weather. The 1998 results were quite typical of what has been seen in the past five years or so.

Exceedances of the 1-hour ozone objective, 1998 (number of hours)

Site	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Customs	0	0	0	0	0	0	0	0	0	0	0	0	0
Forest Hills	0	0	0	0	0	0	0	0	0	0	0	0	0
Hillcrest	0	0	0	0	8	0	0	0	0	0	0	0	8
Canterbury	0	0	0	0	1	0	0	0	0	0	0	0	1
Pt. Lepreau	0	0	0	0	10	1	0	0	0	0	0	0	11
St. Andrews	0	0	0	0	0	0	0	0	0	0	0	0	0
Campobello Isl.	-	-	-	0	6	0	0	0	0	-	-	-	6
Fundy Park	M	M	M	M	M	M	8	0	0	0	M	M	8
Norton	0	0	0	0	0	0	0	0	0	0	0	0	0
Moncton	-	-	-	-	-	-	2	0	0	0	0	0	2
Blissville	0	0	0	0	6	0	0	0	0	0	0	0	6
Total	0	0	0	0	23	1	10	0	0	0	0	0	42

The 1 hour National Objective is 82 ppb. M = missing data. The Campobello site is operated in summer only.

The frequency of ozone episodes (periods of one or more days with high readings) in New Brunswick is dependent on summer weather conditions. Ozone events typically occur when weather systems result in transport of air into the province from the south-west. A greater than normal frequency of west to north-westerly winds results in fewer days with high ozone.

Monthly means and extremes are shown in Appendix III. There is a natural seasonal cycle in ozone levels, with higher values being seen in the spring months. This is due to seasonal patterns in atmospheric circulation. This feature is apparent at most New Brunswick sites. Monthly mean values can be seen to peak in March and April.

10. ACID PRECIPITATION NETWORK

New Brunswick has operated an extensive precipitation chemistry network since the early 1980's. Since 1987, this has been a partnership effort, with logistical and financial support from NB Power. All samples are analysed at the NBDOE laboratory, and DOE staff co-ordinate the monitoring program, perform data quality assurance, and maintain the official data archive.

The potentially adverse impacts of acid precipitation have been recognised for more than 20 years. Acid rain effects are felt regionally, not just close to the sources of contaminants themselves. The emissions which cause acid precipitation (primarily sulphur dioxide and nitrogen oxides) typically travel long distances - hundreds or even thousands of kilometres - before returning to the surface in rain or snow. The same emissions also contribute to regional haze and fine particulate pollution.

Precipitation chemistry in New Brunswick is affected by the emissions from several large industrial regions which lie upwind, including the American midwest, southern Ontario and Quebec, and the Washington-Boston region.

Partly because the site of impact is remote from the point of emission, no standards have been put in place for acid precipitation. Instead, the issue has been managed by the adoption of 'target' or 'critical' loads. These are similar to the objectives used in the management of other air pollutants. Although they are not legally enforceable, they do provide a goal towards which affected US States and Canadian Provinces are working, as emissions are reduced over time.

The severity of acid rain impact is generally measured by computing how much sulphate (a measure of sulphuric acid) falls on each hectare over one year. The target load for acid rain is expressed in terms of this amount of sulphate. In the late 1980's, the proposed target load for eastern Canada was 20 kilograms per hectare per year (kg/ha/yr).

This target was initially designed to provide protection to areas which are moderately sensitive to **acidification**. This sensitivity varies in different areas, because geological characteristics such as soils and bedrock have different abilities to neutralise the acid precipitation. This is often referred to as the 'buffering capacity'.

Over time, scientists realised that these initial target loads were not adequate to provide long term protection, or protect more sensitive watersheds. The newer concept of **critical loads** was introduced in the 1990's. Critical loads take into account the nature of individual watersheds, and are calculated to ensure long term protection from acidification.

Critical loads for acidification in New Brunswick range from 8 to 11 kg/ha/year of sulphate input (referred to as acid sulphate deposition). The value of 8 kg/ha/yr refers to the most sensitive areas on granite bedrock (e.g. areas of southwestern and central northern New Brunswick), and 11 kg/ha/yr to most of the rest of the Province.

In recent years, acidic deposition has been declining slowly. This means that, for the first time since monitoring began in 1980, the critical load values are beginning to be met over some parts of the Province, although still exceeded in others, notably sensitive regions in the south west. There is, however, still more effort required to reduce acid deposition further and ensure that the more sensitive lakes and rivers, such as those in southwestern N.B., are provided with long term protection from acid damage. Further cuts in sulphur dioxide emissions are being pursued, both in the Province and those regions of eastern Canada and the United States which are the main source regions of these acid-causing emissions.

Figure 13 shows the location of monitoring sites, and Figure 14 the acid deposition recorded in 1998. Acid deposition increased in 1998 at many sites compared to 1997. From 1997 to 1998, the average increase in sulphate deposition for the 13 sites in the network was 24.8%: although pollutant concentrations decreased by 15%, precipitation increased an average of 28.9%. Acid deposition, the total amount of a chemical substance entering the environment, is a factor of both concentration in the precipitation and the amount of precipitation received. As a result, there will always be significant variability in acid deposition between years due to variability in weather patterns. Results presented in the following section on long terms trends indicate that when averaged across the province, the concentration of acidic pollutants in precipitation appears to be falling. Although this is encouraging, the data also show that the acid rain issue remains important in New Brunswick, as critical loads for acid rain are still being exceeded, especially in the south.



Figure 13. Location of acid rain monitoring sites in New Brunswick (1998).



Figure 14. Acid Deposition for 1998 (kilograms per hectare per year of sulphate). The droplet symbols are sized in proportion to the deposition measured at that site.

A. New England Governors/Eastern Canadian Premiers Acid Rain Action Plan

Since the early 1980's the New England Governors/Eastern Canadian Premiers have met annually to discuss items of regional interest, such as trade, tourism and the environment. In the 1980's and early 1990's this collaboration led to significant efforts to address the acid rain issue, and develop emission control programs.

In June 1998, the Governors and Premiers met in Fredericton, New Brunswick, and reaffirmed their concern that the acid rain issue was still a concern in the northeastern region. As a result of the meeting, a detailed Acid Rain Action Plan was drafted, listing 22 recommendations. Work has begun under this plan to fill gaps in existing knowledge, improve data sharing, establish new monitoring networks and review emission control efforts. Working groups have been established to address the following items: data collection and management, monitoring of surface water quality and fine particulates in air, forest mapping, sulphur and nitrogen control strategies, and public awareness and education.

B. Canada-Wide Acid Rain Strategy for Post-2000

In October 1998, this strategy was signed by the Ministers of Environment and Energy of all provinces and territories. The Post-2000 Strategy updates efforts which have been going on since the mid 1980's to reduce emissions which contribute to acid rain. Efforts from 1985 to date have reduced sulphur dioxide emissions in eastern Canada by 50% from 1980 levels. The Post-2000 strategy contains plans to reduce acid-causing emissions even further, recognising that although progress has been made, more reductions are still needed to enable critical loads to be reached. The strategy also provides direction for other activities such as scientific monitoring and research, and it makes a formal commitment to seek further reductions in sulphur dioxide emissions from the United States. The need to assess the importance of nitrogen oxides is also noted in the strategy. Annual updates are expected on progress under the Post-2000 strategy, including status reports on yearly pollutant emissions and forecasts, and more details on planned reductions and science programs.

11. LONG TERM AIR POLLUTION TRENDS

In addition to examining air quality monitoring results for a given year, it is often informative and revealing to compare annual results to previous years, and consider longer term trends. This provides information on how air quality may be changing over the years, and whether emission control measures as applied to industrial operations and consumer products (notably vehicles) are influencing long term environmental quality. As mentioned in the introduction, air quality monitoring has been ongoing in parts of the province since the 1970's, especially in the Saint John region. In this section, data for key locations with long-term records are presented to provide information on air quality trends.

A. Carbon Monoxide

The only long term site for this substance is the Customs Building site in uptown Saint John. The earlier part of the record (prior to 1991) is from the nearby Post Office location. Results are predominantly influenced by motor vehicle emissions. Results show that since 1980, the annual average has changed relatively little. There are signs of a possible decrease from 1980 to the mid 1990's, and an increase since then, although the variability between years reduces the confidence that these are meaningful patterns. During the period in question the population of Saint John has increased approximately 4% (Aldighieri, 1998). The number of vehicles registered and more notably, the average total kilometres driven each year, have been increasing throughout the 1990's (Goggin, 1999; Transport Canada, 1999; Statistics Canada, 1999). These pressures, which tend to increase carbon monoxide emissions, have been offset by a greater proportion of vehicles on the road fitted with emissions control equipment, such as catalytic converters. It remains to be seen whether the higher values in the past two years are the beginning of an upward trend.



Figure 15. Annual mean values of carbon monoxide, Post Office/Customs Building, Saint John, 1980-1998.

B. Nitrogen dioxide

Forest Hills

Nitrogen dioxide is another key pollutant emitted by motor vehicles, as well as industrial sources. The trend at Forest Hills, in suburban east Saint John, appears to be downward since 1981, with little variation between years since 1987. Forest Hills is influenced by emissions from local industries as well as the more diffuse sources such as vehicles.



Figure 16. Annual mean nitrogen dioxide at Forest Hills, Saint John, 1981-1998.

Customs Building

At this uptown location, nitrogen dioxide levels appear to be stable or decreasing in recent years, following an increase from the early 1980's to 1987.



Figure 17. Annual mean nitrogen dioxide at Customs Building, Saint John, 1980-1998.

C. Sulphur dioxide

Forest Hills

Air quality monitored at the Forest Hills site in east Saint John is influenced by several local industries. Considering the trend since 1976, annual average concentrations have twice increased and decreased over the 22 year period, from 1976 to 1987 and from 1987 to 1998. Concentrations in the past few years are approximately half what they were in the late 1970s and early 1980's. This is due to a number of factors including changing generation patterns at the Courtenay Bay generating station and reduced emissions from the pulp and paper sector. Other influences on sulphur dioxide levels at the site include emissions from the oil refinery and possibly the Coleson Cove generating station.



Figure 18. Annual mean sulphur dioxide at Forest Hills, Saint John, 1976-1998.

Customs Building

In uptown Saint John, as represented by records from the Post Office and Customs Building sites, the sulphur dioxide trend since the mid-1970's has been overwhelmingly downward. Recently, levels have been approximately 30% of those common in the early 1980's. Decreasing concentrations in this part of the city are probably due to reduced emissions from the Reversing Falls pulp and paper mill, which fell by about 70% from 1980 to 1995. Reduced emissions from the NB Power Courtenay Bay generating station (down 74% from 1990 to 1995) may also be partly responsible.



Figure 19. Annual mean sulphur dioxide at Post Office/Customs Building, Saint John, 1974-1998.

D. Ozone

As explained in section 9, ozone is a regionally transported pollutant which is not emitted directly from smokestacks or tailpipes, but which forms in the air when other pollutants mix and react together. As such, trends in ozone are due to changing emissions of the pollution ingredients that are required for ozone to be made (nitrogen oxides and volatile organic compounds) over a large upwind area of eastern Canada and the United States. Seasonal weather, especially summer conditions, also has a major influence on the amount of ozone affecting New Brunswick.

Forest Hills

At Forest Hills, ozone levels have not changed significantly over the past 19 years. There have been some years such as 1984 and 1988 which had higher values, but there is no overall trend either up or down.



Figure 20. Annual mean ozone at Forest Hills, Saint John, 1980-1998.

Customs Building

At the Downtown Customs site, there are indications of an increase in ozone since 1980. The reasons for this are not clear. Some relationship with other pollutants which react with ozone might be expected. For example nitric oxide, which is emitted by motor vehicles, reacts with ozone to form nitrogen dioxide and oxygen. However there is no apparent relationship between annual ozone and nitrogen dioxide concentrations at this site. There is some evidence of more variable results between years following the local site move from the Post Office to the Customs Building in 1992.



Figure 21. Annual mean ozone at Post Office/Customs Building, 1980-1998.

Point Lepreau

Data for this site are included to provide a perspective from a rural location which is almost always upwind of major sources of air pollutants in southern New Brunswick. Annual ozone levels are somewhat higher than those seen in the Saint John area. This is due to the lack of other emissions which react with and remove ozone from the air (mainly nitric oxide).

The record at Point Lepreau reveals considerable variability between years and the indication of a possible upward trend since 1986. Due to the complex relationship between ozone, its precursor compounds and weather conditions, it is very difficult to evaluate the significance of apparent trends in ozone. Within a given geographic area it is not unusual to find different trends at different sites, even though all may be apparently influenced by the same weather and pollution transport conditions. Local site factors are probably important. The analysis of rural ozone data is still in a relatively early stage of development.



Figure 22. Annual mean ozone at Point Lepreau, 1986-1998.

E. Total Suspended Particulate

Forest Hills

Total suspended particulate levels have generally decreased significantly over the past 20 years, as shown in the record at Forest Hills, east Saint John. Values during the 1990's were less than half what they were in the 1980's. Reductions can be assigned to improved particulate control by industries, cleaner running motor vehicles, and reduced open burning of all kinds.



Figure 23. Annual mean total suspended particulate at Forest Hills, Saint John, 1978-1998.

Provincial Building

Particulate data from the provincial building in uptown Saint John also show a trend which is very similar to that at Forest Hills.



Figure 24. Annual mean total suspended particulate, Provincial Building, Saint John, 1974-1998.

Fredericton

Another long term record for particulate has been maintained at the fire hall on York and Dundonald streets in Fredericton. The site is representative of most of the downtown region.



Figure 25. Annual mean total suspended particulate, Fredericton, 1975-1998.

The Fredericton data reveal a trend very similar to that shown by the Saint John sites. Levels in recent years are about 50-60% of what they were in the late 1970's/early 1980's. Although elevated readings are still seen occasionally, which appear to be due to road dust and possibly also woodsmoke from domestic stoves, the overall trend is clearly downward.

F. PM_{10}

Provincial Building

PM_{10} particulate matter has been measured at a small number of locations, all in Saint John, starting in 1984. The longest records are at the Provincial Building and Forest Hills sites. Data from these locations are presented here.

Averaging over five years, data from the Provincial Building show a decline from 24.5 to 19.5 micrograms/cubic metre from 1984-88 to 1994-98. This decline is consistent with the decrease in total suspended particulate over the same period.



Figure 26. Annual mean PM_{10} at Provincial Building, Saint John, 1984-1998.

Forest Hills

The data from Forest Hills show a proportionally greater drop than those at the Provincial Building - almost 50% since 1989. Due to the effect of dust (especially road dust) on PM_{10}, some variation between years is to be expected, due to changes in weather (for example, the frequency of dry, windy conditions).



Fig..re 27. Annual mean PM_{10} at Forest Hills, Saint John, 1989-1998.

G. Acid Rain

Since 1986, 27 separate sites have been operated for monitoring acid deposition across New Brunswick. Provincial coverage is presently maintained with 13 sites. To provide a statistic which can give some indication of long term changes or trends, the annual average sulphate concentration in precipitation was averaged across all sites operating in each year. The results are shown in the accompanying chart, which also shows the number of sites operating in each year. The apparent trend is downward since 1989. This is expected, based on reductions in sulphur dioxide emissions in eastern Canada and the United States in the same time period.



Figure 28. Network-wide mean annual sulphate concentration in precipitation in New Brunswick, 1986-1998.

12. SUMMARY

The results in this report show that compliance with standards was generally good in 1998, with 100% compliance at many locations, and few sites having compliance rates of less than 95% of the total number of hours measured. Some variation in results is evident between regions and their monitoring networks. This variability is due to many factors including emissions trends, variations in industrial output, changing process or emission control technologies, and the weather conditions experienced in the year in question.

There were no exceedances in 1998 of standards for nitrogen dioxide or carbon monoxide at any of the provincial monitoring sites (seven sites for nitrogen dioxide and two for carbon monoxide). The total number of exceedances of sulphur dioxide standards in the province in 1998 was more than 30% below that in 1997. There was little change in the number of provincial exceedances for hydrogen sulphide, whereas the number of ozone exceedances in 1998 was significantly higher than 1997 (42 versus 8).

In Saint John, where the most stringent sulphur dioxide standards in the Province are in place, which are twice as tough as the National Acceptable Objectives, full compliance was achieved for more than 97% of the time in 1998. Other networks recorded higher peak readings, including some sites in the Belledune Brunswick Mining and Smelting network, the Belledune NB Power Network and the Grand Lake NB Power network.

Exceedances of ambient standards for hydrogen sulphide in the Miramichi network are thought to be due to the effect of emissions from a treatment lagoon, and mitigation work is in progress. In west Saint John, the sporadic hydrogen sulphide exceedances are due in part to the close proximity of the emission source to the monitoring locations.

Air pollution due to particulate matter (TSP and PM_{10}) varied significantly between the various New Brunswick monitoring locations, as revealed most clearly in the annual averages. Such variability is expected, as TSP and PM_{10} are both strongly influenced by local sources of particulate matter, including road dust and smoke from domestic woodstoves. The number of exceedances of provincial standards, or other nationally established objectives, was low at all monitored locations.

New Brunswick's geographic location means that relatively high levels of ozone continue to be recorded here due to long range transport. However, the number of days on which exceedances were seen in 1998 was relatively low.

The same process the long range transport of air pollutants is still producing significant acid rain impacts in the Province, particularly in southwestern districts. New Brunswick is continuing its active dialogue, information-sharing, data analysis and policy activities with neighbouring provinces and US states, to make further progress on both ground level ozone and acid rain prevention.

Examination of long term air quality trends at a number of sites showed that air quality has improved since the late 1970's/early 1980's. Downward trends in particulate matter and sulphur dioxide were especially notable. The only pollutant with negligible improvement appears to be ground level ozone.

New Brunswick's good air quality has much to do with the lack of large urban centres in this province, which means that the pollution associated with 'big city' levels of traffic and other pollution sources, is not present in our Province. It is also a reflection of the successful environmental management of major air pollution sources within New Brunswick.

Consistent with the guiding principles stated in the *Clean Air Act*, which place considerable emphasis on sustainability, the goal of the NBDOE's air quality management policy is to strive towards 100% compliance with all applicable standards, and wherever practicable, to go beyond this and reduce the emission of contaminants to the greatest possible degree.

APPENDIX I: GLOSSARY OF TERMS AND ABBREVIATIONS

micrograms/m3	Microgram (of contaminant) per cubic metre (of air).
Two-way catalytic converter	A device fitted to motor vehicle exhaust systems which reduces their output of air pollutants. A 2-way converter is designed to reduce the carbon monoxide and hydrocarbon emissions. Fitted to new light duty motor vehicles sold in Canada after 1974.
Three-way catalytic converter	A 3-way converter reduces nitrogen oxides (NOx) from motor vehicle exhaust, in addition to the pollutants removed by a 2-way catalytic converter. Fitted to new light duty motor vehicles sold in Canada after 1987.
Acidic deposition	The input of acidic pollutants to the environment, usually expressed as kilograms per hectare per year of acid-forming substances such as sulphates and nitrates (see acid rain).
Acid rain	A term which refers to rain (and snow) which has become abnormally acidic due to the effects of acidifying gases such as sulphur dioxide and nitrogen dioxide.
Acid aerosols	Very small (usually invisible) airborne particles which contain acids.
Acidification	The process by which lakes, rivers or whole drainage basins can be adversely affected by continued inputs of acid rain.
Act	A broad piece of legislation which provides authority to government departments and Ministers to develop more specific regulations and policies, and carry out related enforcement activities.
Aerosol	When referring to air pollution, aerosol means small suspended particles in the air, which may be natural or resulting from human activities.
Air quality Index	A near real-time information system providing the public with an indication of overall air quality, expressed as a single number (usually on a 0-100 scale). The index takes into account measurements of several pollutants.
Ambient air	Outdoor air.
Approval to Operate	A permit issued to businesses which tells them what they must do to comply with environmental protection requirements. For example these permits specify allowable emissions of various substances, how often reports must be made to the NBDOE, what these reports must contain, and mandatory annual testing.
ARMA committee	Air Resource Management Area Committee. Several such committees have been formed in New Brunswick since 1994, to examine local air quality issues and submit recommendations to the Minister of the Environment.
Asthma	A disorder of the respiratory system, associated with difficulty in breathing.
Bronchitis	Inflammation of the small bronchial tubes in the lungs, which may be associated with breathing difficulties, discomfort or coughing.
Carbon monoxide	Abbreviation: CO. A colourless, odourless, toxic gas formed when fuels burn inefficiently.

CO	Carbon monoxide.
Cardiovascular	Having to do with the heart and blood circulation system.
Catalytic converter	In a motor vehicle, a device for converting harmful exhaust gases into less harmful substances. These converters use a chemical catalyst which causes the chemical conversion to take place. See 2- and 3-way catalytic converter.
Certificate of Approval	See Approval to Operate.
Clean Air Strategy	A policy document of the NBDOE, published in 1993, reviewing air quality in New Brunswick and setting out directions for future efforts to improve it.
Corridor	In air pollution terminology, refers to a region through which prevailing winds frequently pass, carrying air pollutants. For example the Windsor-Quebec City corridor, the Washington-Boston corridor.
Critical load	Referring to acid rain, the amount of acid input a region can receive which results in no long term adverse affects to at least 95% of its lakes.
Emphysema	A condition in which the air sacs in the lungs are abnormally enlarged, causing lack of breath.
Episode control program	An agreed-upon system of actions to be taken by anindustry or other source or air contaminants, designed to prevent the occurrence of exceedances.
Exceedance	When referring to air pollution, an occasion on which a specified air quality standard or objective was surpassed. Note that hourly exceedances refer to measurements made over standard clock hours.
Geometric mean	A way of calculating a meaningful average from data which contains extreme values.
Ground level ozone	Ozone found in the air in the lower atmosphere, including the air we breathe. See ozone.
Guideline	A recommended value, but one which usually does not have the force of law. See objective.
H_2S	Hydrogen sulphide.
Hydrocarbon	A compound containing only hydrogen and carbon. For example methane, propane and butane are all hydrocarbons.
Hydrogen sulphide	Abbreviation: H_2S. A toxic gas, smelling powerfully of rotten eggs, detectable by the human nose at very low concentrations. Formed by some paper making processes and also found in sewer gases and naturally in swamps and marshes, where it is produced by decomposing plants.
Inhalable particles	Particles of soot, dust etc., which are small enough that they may enter the lungs without being filtered out by the nose and throat.
IQUA	Index of the Quality of the Air. A system used in Saint John since 1979 to provide the public with a reference indicator for air quality. See Air Quality Index.

kg	Kilogram.
Long range transport	In air pollution terminology, refers to the movement of air pollutants by prevailing winds and weather systems hundreds or thousands of kilometres from where they are released.
Microgram	A millionth of a gram.
Modelling	In the context of air pollution, this terms refers to computer modelling: using simulations of the atmosphere and other natural processes to explore the probable outcome of changing pollution emissions, or the impact of other factors such as weather on pollution levels.
NAAQO	National Ambient Air Quality Objective. Nationally recommended guideline concentrations for air contaminants, designed to provide protection of human health and the environment generally.
NBDOE	The New Brunswick Department of the Environment.
Nitrogen oxides	Compounds of nitrogen and oxygen, primarily referring to nitric oxide and nitrogen dioxide. Abbreviation: NOx.
NOx	See nitrogen oxides.
NO_2	Nitrogen dioxide.
Objective	In the context of air quality, a management goal for environmental protection, usually stated as a number (see the definition for guideline). Objectives may also be broader in nature and expressed as plain language statements. Objectives do not normally have legal force.
Ozone	Abbreviation: O_3. A colourless gas, formed from three oxygen atoms, having a sharp odour at high concentrations. Ozone is very chemically active and can damage living plant and animal cells. Ozone is a major component of photochemical smog, and is formed in this situation by reactions between other air pollutants.
O_3	Ozone
Particulate	A very small piece of soot, smoke or dust; by inference, one which is small enough to become airborne.
Photochemical smog	A mixture of air pollutants usually containing ozone, nitrogen oxides, and particulates. Seen over or downwind of major city areas, typically in hot, sunny weather together with light winds. Often visible against a clear sky as a whitish, yellow or brown cloud or layer.
ppb	Parts (of contaminant) per billion (parts of air).
ppm	Parts (of contaminant) per million (parts of air).
pphm	Parts (of contaminant) per hundred million (parts of air).
PM_{10}	Particulate matter where the individual particles have an effective diameter of 10 microns (millionths of a metre) or less. These particles are small enough to be bypass filtration by the nose and may enter the lungs.

$PM_{2.5}$	Particulate matter where the individual particles have an effective diameter of 2.5 microns (millionths of a metre) or less. These particles may be deposited in the lungs if inhaled.
Radiation balance	The process by which the earth remains at a more or less constant temperature, by radiating as much heat into space as it receives from the sun. So-called greenhouse gases (such as carbon dioxide or methane) affect this balance by slowing down the loss of heat from the lower atmosphere.
Regulation	A formal legal document, made with the authority of an Act, which specifies rules in more technical detail than is given in the Act itself.
Smog advisory	A public information message providing details of expected ground level ozone pollution in the following 24 hours. A smog advisory program has operated in New Brunswick since 1993.
Smog	Originally, a mixture of smoke and fog. Now more often used to refer to pollution mixtures containing ozone and fine particles. See photochemical smog.
SO_2	Sulphur dioxide.
Standard	A numeric value used for the purpose of environmental management: usually refers to an acceptable concentration of a contaminant. Differs from a guideline, goal or objective by having legal force.
Sulphur dioxide	A gas generated when sulphur-containing fuels are burned, having a characteristic, acrid smell. One of the most widespread air pollutants around the world, associated with heavy industry (e.g. smelting, oil refining and major fuel combustion in generating stations).
Target load	Referring to the issue of acid deposition, an interim goal for environmental protection.
TEOM	A type of continuous measuring device for monitoring the particulate content of ambient air. Refers to the measurement principle (Tapered Element Oscillating Microbalance).
TSP	Total suspended particulate.
Total suspended particulate	Abbreviation: TSP. A standard measure of particle concentration in the air. Includes smoke, soot, pollen and other dust from about 0.1 up to approx. 50 microns in diameter.
Trajectory analysis	A method for following the movement of air over long distances, enabling the probable source regions of pollutants to be identified.
VOC	Abbreviation for volatile organic compound. Includes carbon-containing substances which evaporate readily at normal environmental temperatures, examples include gasoline, the solvents in paint, nail polish remover, and many natural VOCs.

APPENDIX II: CANADIAN NATIONAL AIR QUALITY OBJECTIVES

Canadian National Air Quality Objectives

		Sulphur Dioxide	TSP	Carbon Monoxide	Ozone	Nitrogen Dioxide	Hydrogen Sulphide
		ppb	$\mu g/m^3$	ppm	ppb	ppb	ppb
Maximum Tolerable Level	1 h				153	532	
	8 h			17.5			
	24 h	306	400			160	
	1 yr.						
Maximum Acceptable Level	1 h	344		30.6	82	213	10.8
	8 h			13.1			
	24 h	115	120		25	106	3.6
	1 yr.	23	70		15	53	
Maximum Desirable Level	1 h	172		13.1	51		0.7
	8 h			5.2			
	24 h	57			15		
	1 yr.	11	60			0.03	

Notes:
1. The maximum tolerable level denotes a concentration of an air pollutant that requires abatement without delay to avoid further deterioration to air quality that poses a substantial risk to public health.
2. The acceptable level is intended to provide adequate protection against adverse effects on soil, water, vegetation, materials, animals, visibility, personal comfort and well being.
3. The desirable level defines the long-term goal for air quality and provides the basis for an anti-degradation policy for the unpolluted parts of the country.

TSP : Total suspended particulate.

$\mu g/m_3$: Micrograms per cubic metre.

APPENDIX III

DETAILED MONTHLY MONITORING RESULTS FOR 1998

Monthly Average and Maximum One Hour Values of Carbon Monoxide in 1998
Customs Building - Saint John



Monthly Average and Maximum One Hour Values of Carbon Monoxide in 1998
Highfield St. - Moncton



Monthly Average and Maximum One Hour Values of Hydrogen Sulphide in 1998
West Side Station (Hillcrest)



Monthly Average and Maximum One Hour Values of Total Reduced Sulphur in 1998
Indian Town - Saint John



Monthly Average and Maximum One Hour Values of Total Reduced Sulphur in 1998
Milford - Saint John



Monthly Average and Maximum One Hour Values of Total Reduced Sulphur in 1998
Sherbrooke Street - Saint John



Monthly Average and Maximum One Hour Values of Total Reduced Sulphur in 1998
REPAP - Groundwood Mill



Monthly Average and Maximum One Hour Values of Total Reduced Sulphur in 1998
REPAP - King George Highway



Monthly Average and Maximum One Hour Values of Nitrogen Dioxide in 1998
Customs Building - Saint John



Monthly Average and Maximum One Hour Values of Nitrogen Dioxide in 1998
Forest Hills - Saint John



Monthly Average and Maximum One Hour Values of Nitrogen Dioxide in 1998
Highfield St. - Moncton



Monthly Average and Maximum One Hour Values of Nitrogen Dioxide in 1998
NB Power Belledune - Belledune East



Monthly Average and Maximum One Hour Values of Nitrogen Dioxide in 1998
NB Power Belledune - Municipal Hall



Monthly Average and Maximum One Hour Values of Nitrogen Dioxide in 1998
NB Power Millbank - Lower Newcastle



Monthly Average and Maximum One Hour Values of Nitrogen Dioxide in 1998
NB Power Millbank - Rockcliff



Monthly Average and Maximum One Hour Values of Ozone in 1998
Customs Building - Saint John



Monthly Average and Maximum One Hour Values of Ozone in 1998
Forest Hills - Saint John



Monthly Average and Maximum One Hour Values of Ozone in 1998
Canterbury



Monthly Average and Maximum One Hour Values of Ozone in 1998
Central Blissville



Monthly Average and Maximum One Hour Values of Ozone in 1998
Fundy National Park




Monthly Average and Maximum One Hour Values of Ozone in 1998
Norton
1 hour objective is 82 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
28 39 28 41 30 54 33 56 30 81 29 61 30 81 27 74 20 60 26 52 23 40 27 51


Monthly Average and Maximum One Hour Values of Ozone in 1998
Pt. Lepreau
1 hour objective is 82 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
28 39 30 40 34 57 33 49 35 107 31 89 34 80 33 67 26 69 27 54 28 41 32 53


Monthly Average and Maximum One Hour Values of Ozone in 1998
West Side Station - Saint John
1 hour objective is 82 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
29 45 30 47 34 60 33 53 36 103 31 64 31 69 31 65 25 67 24 61 24 43 25 50


Monthly Average and Maximum One Hour Values of Ozone in 1998
St. Andrews
1 hour objective is 82 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
21 33 20 28 26 44 27 44 24 75 15 52 17 68 19 37 12 44 12 34 12 26 14 29

Monthly Average and Maximum One Hour Values of Ozone in 1998
Campobello

Monthly Average and Maximum One Hour Values of Ozone in 1998
Highfield St. - Moncton



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Champlain Heights - Saint John



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Customs Building - Saint John




Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Forest Hills - Saint John
Concentration in parts per billion
0 50 100 150 200 250 300
1 hour standard is 170 ppb
9 148 5 245 7 117 6 101 15 144 12 118 22 381 19 172 11 163 4 84 2 37 10 121
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
Month


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Forest Products-Saint John
Concentration in parts per billion
0 50 100 150 200 250 300
1 hour standard is 170 ppb
18 262 10 112 8 166 7 185 5 107 3 53 2 139 2 22 8 173 12 401 18 164 21 135
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
Month


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
West Side Station (Hillcrest)-Saint John
Concentration in parts per billion
0 50 100 150 200 250 300
1 hour standard is 170 ppb
9 110 9 86 4 55 3 58 2 96 1 36 2 43 3 37 5 83 6 101 5 71 7 63
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
Month


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Silver Falls - Saint John
Concentration in parts per billion
0 50 100 150 200 250 300
1 hour standard is 170 ppb
3 162 4 36 7 161 6 122 10 105 8 127 10 183 12 92 11 129 5 98 2 62 4 74
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
Month

Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Three Mile Irving -Saint John



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Brunswick Mining and Smelting - Airstrip



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Brunswick Mining and Smelting - Boulay



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Brunswick Mining and Smelting - Chalmers




Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Brunswick Mining and Smelting - Townsite
1 hour standard is 340 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
3 162 8 560 6 267 10 331 18 319 20 420 10 262 5 142 6 225 6 126 4 81 2 89


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Fraser - Cormier
1 hour standard is 340 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
9 103 10 115 9 108 2 331 9 127 10 203 11 112 14 162 13 221 11 84 11 125 9 102


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
Fraser - Sacred Heart
1 hour standard is 340 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
5 143 6 74 3 64 4 55 3 61 3 71 3 42 4 108 5 114 4 42 5 58 7 91


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Belledune - Belledune East
1 hour standard is 340 ppb
Concentration in parts per billion
Month
Jan Feb Mar Apr May June July Aug Sept Oct Nov Dec
0 470 10 410 10 310 10 430 0 170 0 170 0 160 10 160 0 70 0 140 0 90 0 160

Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Belledune - Jacquet River



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Belledune - Madran



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Belledune - Municipal Hall



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Belledune - Pointe-Verte



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Carleton



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Chario



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Dalhousie High



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Dalhousie Tower



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Miguasha



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Mobile



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Pointe-a-la-Garde



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Dalhousie - Point la Nim




Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Grand Lake - Bailey Point
1 hour standard is 340 ppb
Concentration in parts per billion
400
350
300
250
200
150
100
50
0
240
132
163
138
117
46
136
226
152
325
257
254
5
3
5
3
3
2
3
5
3
5
8
7
Jan
Feb
Mar
Apr
May
June
July
Aug
Sept
Oct
Nov
Dec
Month


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Grand Lake - Cox Point
1 hour standard is 340 ppb
Concentration in parts per billion
400
350
300
250
200
150
100
50
0
124
128
50
71
401
50
5
327
121
123
225
150
4
4
2
3
4
1
1
2
6
4
5
6
Jan
Feb
Mar
Apr
May
June
July
Aug
Sept
Oct
Nov
Dec
Month


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Grand Lake - Flower's Cove
1 hour standard is 340 ppb
Concentration in parts per billion
400
350
300
250
200
150
100
50
0
285
327
272
201
191
83
122
240
138
255
190
265
17
11
10
10
14
2
2
3
2
8
2
5
Jan
Feb
Mar
Apr
May
June
July
Aug
Sept
Oct
Nov
Dec
Month


Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Grand Lake - Newcastle Centre
1 hour standard is 340 ppb
Concentration in parts per billion
400
350
300
250
200
150
100
50
0
72
234
281
117
363
260
271
405
294
350
258
271
3
3
6
3
10
3
6
13
8
7
2
4
Jan
Feb
Mar
Apr
May
June
July
Aug
Sept
Oct
Nov
Dec
Month

Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Millbank - Rockcliff



Monthly Average and Maximum One Hour Values of Sulphur Dioxide in 1998
NB Power Millbank - Lower Newcastle



Daily TSP for 1998
Forest Hills - Saint John



Daily TSP for 1998
Police Station - Fredericton




Daily TSP for 1998
Provincial Building - Saint John
24 hour standard is 120 micrograms per cubic metre
Some missing data for June, July and August
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month


Daily TSP for 1998
NB Power Dalhousie - Dalhousie Tower
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month


Daily TSP for 1998
NB Power Dalhousie - Coal Berm Site
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month


Daily TSP for 1998
Fraser - Cormier
24 hour standard is 120 micrograms per cubic metre
207
210
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month

Daily TSP for 1998
Fraser - Sacred Heart



Daily TSP for 1998
NB Power Grand Lake - Flowers Cove



Daily TSP for 1998
NB Power Grand Lake - Newcastle Centre



Daily TSP for 1998
NB Power Grand Lake - Bailey Point




Daily TSP for 1998
NB Power Grand Lake - Cox Point
24 hour standard is 120 micrograms per cubic metre
Missing data for July
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month


Daily TSP for 1998
NB Power Millbank - Rockcliff
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month


Daily TSP for 1998
NB Power Millbank - Lower Newcastle
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month


Daily TSP for 1998
REPAP - King George Highway
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month


Daily TSP for 1998
REPAP - Groundwood Mill
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan
Feb
Mar
Apr
May
Jun
Jul
Aug
Sep
Oct
Nov
Dec
Month


Daily TSP for 1998
REPAP - South Esk
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan
Feb
Mar
Apr
May
Jun
Jul
Aug
Sep
Oct
Nov
Dec
Month


Daily TSP for 1998
Brunswick Mining and Smelting - Airfield
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan
Feb
Mar
Apr
May
Jun
Jul
Aug
Sep
Oct
Nov
Dec
Month


Daily TSP for 1998
Brunswick Mining and Smelting - Townsite
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan
Feb
Mar
Apr
May
Jun
Jul
Aug
Sep
Oct
Nov
Dec
Month



Daily TSP for 1998
Brunswick Mining and Smelting - Chalmers
24 hour standard is 120 micrograms per cubic metre
Concentration in micrograms per cubic metre
0
50
100
150
200
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month



Daily PM10 for 1998
Forest Hills - Saint John
24 hour standards:
50 (Vancouver, California) 150 (USA)
Concentration in micrograms per cubic metre
0
50
100
150
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month



Daily PM10 for 1998
Provincial Building - Saint John
24 hour standards:
50 (Vancouver, California) 150 (USA)
Concentration in micrograms per cubic metre
0
50
100
150
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month



Daily PM10 for 1998
Hillcrest - Saint John
24 hour standards:
50 (Vancouver, California) 150 (USA)
Concentration in micrograms per cubic metre
0
50
100
150
Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Month

Daily PM10 for 1998

Western District Police - Saint John



PM-10 Data-1998

Annual Mean Values



TSP Data-1998

Annual Mean Values



REFERENCES

Aldighieri, A.M. (Ed.) 1998. Canadian Almanac and Directory. Micromedia, Toronto.

Bates, D.V., 1980. The health effects of air pollution. J. Respir. Disease 1: 29-37.

Blomberg, A., 1998. Respiratory effects of atmospheric pollutants: from science to the clinic. Presentation at the ERS/98 Symposium, Geneva, Switzerland, reproduced on the ENVENG internet mailing list, September 27, 1998.

CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1987a. Review of national ambient air quality objectives for nitrogen dioxide; desirable and acceptable levels. Environment Canada, Conservation and Protection, Ottawa, 24 pp.

CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1987b. Review of national ambient air quality objectives for sulphur dioxide; desirable and acceptable levels. Environment Canada, Conservation and Protection, Ottawa, 31 pp.

CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1994. National ambient air quality objectives for carbon monoxide. Minister of Public Works and Government Services Canada, 161 pp.

CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1998. National ambient air quality objectives for particulate matter. Minister of Public Works and Government Services Canada.

CEPA/FPAC Working Group on Air Quality Objectives and Guidelines, 1998. National ambient air quality objectives for carbon monoxide: Desirable, acceptable and tolerable levels. Minister of Public Works and Government Services Canada, Ottawa, 161 pp.

Commission for Environmental Cooperation, 1997. Long-range transport of ground-level ozone and its precursors: Assessment of methods to quantify transboundary transport within the northeastern United States and eastern Canada. Commission for Environmental Cooperation, Montréal, Québec, 108 pp.

Delauriers, M., 1996. Canadian emissions inventory of criteria air contaminants (1990). Environment Canada, Ottawa; Environmental Protection Series, Report EPS 5/AP/7E.

Environment Canada, 1984. Hydrogen sulphide: Environmental and technical information for problem spills. Environmental Protection Service, Ottawa, 112 pp.

Environment Canada, 1985. Sulphur dioxide, Environmental and technical information for problem spills. Environmental Protection Service, Ottawa, 111 pp.

Environment Canada, 1998. National Pollutant Release Inventory, Canadian Environmental Protection Act, Summary Report, 1996. 226 pp.

Jaques, A., F. Neizert and P. Boileau, 1997. Trends in Canada's greenhouse gas emissions, 1990-1995. Environment Canada, Air Pollution Prevention Directorate, Ottawa.

Masters, G.M., 1997. Introduction to environmental engineering and science, 2nd Edition. Prentice-Hall, Upper Saddle River, NJ, 651 pp.

Multistakeholder NOx/VOC Science Program, 1997a. Canadian NOx/VOC Science Assessment: Ground level ozone and its precursors, 1980-1993. Report of the Data Analysis Working Group, Dann, T. and P. Summers, Eds. 295 pp.

Multistakeholder NOx/VOC Science Program, 1997b. Canadian NOx/VOC Science Assessment: Modelling of ground-level ozone in the Windsor-Québec City corridor and in the southern Atlantic region. Report of the WQC Corridor and Southern Atlantic Region Modelling Working Group. Venkatesh, S. and B. Beattie, Eds. 265 pp.

Multistakeholder NOx/VOC Science Program, 1997c. Canadian NOx/VOC Science Assessment: Report of the Health Objective Working Group, Wilby, K, G. Wood and D. Galarneau, Eds., 109 pp.

Ritchie, I., 1991. Introduction to indoor air quality: a reference manual. Washington, D.C. US Environmental Protection Agency, EPA/400-3-91-003.

Statistics Canada, 1999. Information on transport statistics taken from website: http://www.statcan.ca/english/Pgdb/Economy/Communications/trade14.htm.

Stewart, R.L., 1975. The effect of carbon monoxide on humans. Ann Rev. Pharmacol. 15: 409-423.

Tordon, R., P. George, S.T. Beauchamp and K. Keddy, 1994. Source sector analysis of ozone exceedance trajectories in the Maritime region (1980-1993). Environment Canada, Atmospheric Environment Service, Report MAES 2-94, 60 pp.

Transport Canada, 1999. Information on transport statistics taken from web site: http://www.tc.gc.ca/tfacts/anre1998/TC9806DE.HTM.

US EPA, 1980. Significant harm levels for carbon monoxide. Research Triangle Park, NC, Office of Air Quality Planning and Standards.

Wilson, R. and J. D. Spengler (Eds.), 1996. Particles in our air: concentrations and health effects. Harvard University Press, 259 pp.